PROJECT SHEET NO. 38

P L A N

CHAINAGE (M)	CUT/FILL (M)	FORMATION LEVEL (M)	GROUND LEVEL (M)	REVISED CHAINAGE (M)
25000.0	5.793	96.4	90.607	291155
25050.0	5.4	96.6	91.2	291205
25100.0	5.07	96.8	91.73	291255
25150.0	4.94	97.0	92.06	291305
25200.0	4.96	97.2	92.24	291355
25250.0	4.94	97.4	92.46	291405
25300.0	4.93	97.6	92.67	291455
25350.0	4.85	97.8	92.95	291505
25400.0	4.84	98.0	93.16	291555
25450.0	4.77	98.2	93.43	291605
25500.0	4.67	98.4	93.73	291655
25550.0	4.6	98.6	94.0	291705
25600.0	4.54	98.8	94.26	291755
25650.0	4.49	99.0	94.51	291805
25700.0	4.44	99.2	94.76	291855
25750.0	4.39	99.4	95.01	291905
25800.0	4.35	99.6	94.65	291955
25850.0	5.66	99.8	94.14	292005
25900.0	6.05	99.8	93.75	292055
25950.0	7.0	99.6	92.6	292105
26000.0	7.46	99.4	91.94	292155
26050.0	6.08	99.2	93.12	292205
26100.0	4.57	99.0	94.43	292255
26150.0	5.67	98.8	93.13	292305
26200.0	5.83	98.6	92.77	292355
26250.0	4.22	98.4	94.18	292405
26300.0	4.58	98.2	93.62	292455
26350.0	4.84	98.0	93.16	292505
26400.0	4.18	97.8	93.64	292555
26450.0	4.08	97.6	93.54	292605
26500.0	4.02	97.4	93.38	292655
26550.0	4.01	97.2	93.19	292705
26600.0	3.98	97.0	93.02	292755
26650.0	3.92	96.8	92.88	292805
26700.0	3.86	96.6	92.74	292855
26750.0	3.78	96.4	92.62	292905
26800.0	3.61	96.2	92.59	292955
26850.0	3.25	96.0	92.75	293005
26900.0	2.9	95.8	92.9	293055
26950.0	2.8	95.8	93.0	293105
27000.0	2.74	95.8	93.06	293155
27050.0	2.83	95.8	92.97	293205
27100.0	2.81	95.8	92.99	293255
27150.0	2.858	95.858	93.04	293305
27200.0	3.033	96.093	93.06	293355
27250.0	3.188	96.288	93.1	293405
27300.0	3.383	96.483	93.1	293455
27350.0	3.469	96.679	93.21	293505
27400.0	3.664	96.874	93.21	293555
27450.0	3.839	97.069	93.23	293605
27500.0	3.864	97.264	93.38	293655
27550.0	4.18	97.46	93.28	293705
27600.0	4.365	97.655	93.29	293755
27650.0	3.93	97.85	93.92	293805
27700.0	4.565	97.845	93.28	293855
27750.0	4.12	97.44	93.32	293905
27800.0	3.766	97.236	93.47	293955
27850.0	3.631	97.031	93.4	294005
27900.0	3.326	96.826	93.5	294055
27950.0	3.081	96.621	93.54	294105
28000.0	2.887	96.417	93.53	294155
28050.0	2.622	96.212	93.59	294205
28100.0	2.457	96.007	93.55	294255
28150.0	1.972	95.802	93.83	294305
28200.0	1.848	95.778	93.93	294355
28250.0	1.903	95.833	94.03	294405
28300.0	1.969	96.089	94.12	294455
28350.0	2.224	96.244	94.02	294505
28400.0	2.48	96.4	93.92	294555
28450.0	2.596	96.556	93.96	294605
28500.0	2.711	96.711	94.0	294655
28550.0	2.827	96.867	94.04	294705
28600.0	2.882	97.022	94.14	294755
28650.0	2.82	97.09	94.27	294805
28700.0	2.711	97.071	94.36	294855
28750.0	2.642	97.052	94.41	294905
28800.0	2.572	97.032	94.46	294955
28850.0	2.523	97.013	94.49	295005
28900.0	2.444	96.994	94.55	295055
28950.0	2.344	96.974	94.63	295105
29000.0	2.265	96.955	94.69	295155
29050.0	2.395	96.935	94.54	295205
29100.0	2.266	96.916	94.65	295255
29150.0	2.087	96.897	94.81	295305
29200.0	2.077	96.877	94.8	295355
29250.0	2.188	96.858	94.67	295405
29300.0	2.319	96.839	94.52	295455
29350.0	2.229	96.819	94.59	295505
29400.0	2.22	96.8	94.58	295555
29450.0	2.311	96.781	94.47	295605
29500.0	2.651	96.761	94.11	295655
29550.0	2.242	96.742	94.5	295705
29600.0	1.923	96.723	94.8	295755
29650.0	2.053	96.703	94.65	295805
29700.0	1.904	96.684	94.78	295855
29750.0	1.955	96.685	94.71	295905
29800.0	2.655	96.645	93.99	295955
29850.0	2.496	96.626	94.13	296005
29900.0	2.436	96.606	94.17	296055
29950.0	2.567	96.587	94.02	296105
30000.0	2.568	96.568	94.0	296155

LONGITUDINAL SECTION

INDICATIVE DRAWING

NOTE:-
MINIMUM HEIGHT OF EMBANKMENT SHALL BE PROVIDED AS PER RELEVANT PARA OF PART II OF BID DOCUMENT.

L E G E N D

EXIST. IR TRACK	
PROP. DFCC TRACK	
EXIST. LAND BOUNDARY	
DFC LAND BOUNDARY	
PROPOSED BRIDGE	
PROP. STRUCTURE	
EXIST. STRUCTURE	
RIVER/NALA	
WELL	
TREE/TREE CLUSTER	
COMPOUND WALL	
WORK TO BE DISMANTLED	
HIGH TENSION LINE	
POND	
TELEPHONE POLE	
ELECTRIC LINE	
OHE TOWER	
HAND PUMP	
GPS PILLAR	
RAILWAY SIGNAL	
OHE MAST	
RELIGIOUS STRUCTURE	
IOC PIPE LINE CORRIDOR	IOC_PIPE_LINE / IOC_PIPE_LINE
ROAD	

DEDICATED FREIGHT CORRIDOR CORPORATION OF INDIA LTD
(A GOVERNMENT OF INDIA ENTERPRISE)

EASTERN CORRIDOR

PROJECT: NEW KARCHANA TO NEW BHAUPUR(EASTERN CORRIDOR) From Ch 278155 to Ch 507693

CONTRACT PACKAGE - 202

TITLE: PLAN AND PROFILE (Ch 291155 to Ch 296155)

SCALE: HORI. 1:5000 VER 1:500

DRAWING NO.: MON/RAIL/ALD

SURVEYORS AND CONTRACTORS Pvt. Ltd.
27, PANDEYA PURI No.1, BALURI LANE(PART)
NEAR SARASWATI SHALL, NEERAJA ROAD
KOLKATA-700 084

GENERAL CONSULTANT
AECOM Asia Co. Ltd.
9TH FLOOR, INFINITY TOWER C DLF CYBER CITY
DLF PHASE II GURGAON 122002, INDIA