PROJECT SHEET NO. 35

PLAN

LONGITUDINAL SECTION

REVISED CHAINAGE (M)	CUT/FILL (M)	FORMATION LEVEL (M)	GROUND LEVEL (M)	CHAINAGE (M)
276155	4.085	97.506	93.421	10000.0
276205	3.695	97.3	93.605	10050.0
276255	3.607	97.37	93.763	10100.0
276305	3.629	97.44	93.811	10150.0
276355	3.675	97.51	93.835	10200.0
276405	3.721	97.58	93.859	10250.0
276455	4.774	97.65	92.876	10300.0
276505	6.028	97.492	91.464	10350.0
276555	5.115	97.333	92.183	10400.0
276605	3.742	97.175	93.433	10450.0
276655	3.1	97.017	93.917	10500.0
276705	2.883	96.858	93.975	10550.0
276755	2.841	96.7	93.859	10600.0
276805	2.977	96.542	93.565	10650.0
276855	2.985	96.383	93.398	10700.0
276905	2.852	96.225	93.373	10750.0
276955	3.235	96.067	92.832	10800.0
277005	4.101	95.908	91.807	10850.0
277055	4.479	95.75	91.271	10900.0
277105	4.297	95.592	91.295	10950.0
277155	4.01	95.433	91.423	11000.0
277205	3.581	95.275	91.694	11050.0
277255	3.073	95.117	92.044	11100.0
277305	2.553	94.958	92.405	11150.0
277355	2.047	94.8	92.753	11200.0
277405	1.878	94.685	93.107	11250.0
277455	1.707	95.17	93.463	11300.0
277505	1.537	95.356	93.819	11350.0
277555	1.366	95.541	94.175	11400.0
277605	1.195	95.726	94.531	11450.0
277655	1.079	95.911	94.832	11500.0
277705	1.237	96.097	94.86	11550.0
277755	1.457	96.282	94.825	11600.0
277805	1.676	96.467	94.791	11650.0
277855	1.896	96.652	94.756	11700.0
277905	2.117	96.838	94.721	11750.0
277955	2.377	97.023	94.646	11800.0
278005	2.611	97.208	94.597	11850.0
278055	3.285	97.393	94.108	11900.0
278105	3.708	97.578	93.82	11950.0
278155	4.233	97.764	93.531	12000.0
278205	4.398	97.641	93.243	12050.0
278255	4.489	97.443	92.954	12100.0
278305	4.58	97.246	92.666	12150.0
278355	4.609	97.048	92.439	12200.0
278405	4.585	96.85	92.265	12250.0
278455	4.553	96.652	92.099	12300.0
278505	4.512	96.455	91.943	12350.0
278555	4.44	96.257	91.817	12400.0
278605	4.361	96.059	91.698	12450.0
278655	4.148	95.861	91.713	12500.0
278705	4.006	95.664	91.658	12550.0
278755	4.849	95.466	90.617	12600.0
278805	5.927	95.268	89.341	12650.0
278855	6.437	95.071	88.634	12700.0
278905	7.551	94.873	87.322	12750.0
278955	7.912	94.675	86.763	12800.0
279005	6.487	94.477	88.01	12850.0
279055	4.69	94.28	89.62	12900.0
279105	3.945	94.082	90.137	12950.0
279155	5.638	93.884	88.246	13000.0
279205	6.388	93.686	87.318	13050.0
279255	6.468	93.489	87.021	13100.0
279305	6.312	93.291	86.979	13150.0
279355	6.176	93.093	86.917	13200.0
279405	6.187	92.895	86.708	13250.0
279455	6.232	92.698	86.466	13300.0
279505	6.102	92.5	86.398	13350.0
279555	6.152	92.653	86.481	13400.0
279605	6.071	92.767	86.696	13450.0
279655	5.896	92.9	87.004	13500.0
279705	5.74	93.033	87.293	13550.0
279755	5.657	93.167	87.51	13600.0
279805	5.854	93.3	87.446	13650.0
279855	6.373	93.433	87.06	13700.0
279905	6.602	93.567	86.965	13750.0
279955	6.835	93.7	86.865	13800.0
280005	7.218	93.7	86.482	13850.0
280055	7.848	93.7	85.852	13900.0
280105	9.208	93.7	84.402	13950.0
280155	10.485	93.7	83.215	14000.0
280205	11.441	93.7	82.259	14050.0
280255	12.544	93.7	81.156	14100.0
280305	15.059	93.7	78.641	14150.0
280355	17.142	93.7	76.558	14200.0
280405	18.18	93.7	75.52	14250.0
280455	19.009	93.7	74.691	14300.0
280505	19.837	93.7	73.863	14350.0
280555	20.443	93.7	73.257	14400.0
280605	19.001	93.7	74.699	14450.0
280655	17.074	93.7	76.626	14500.0
280705	15.147	93.7	78.553	14550.0
280755	13.22	93.7	80.48	14600.0
280805	9.888	93.7	83.812	14650.0
280855	13.845	93.7	82.855	14700.0
280905	9.259	93.7	84.441	14750.0
280955	7.798	93.7	85.902	14800.0
281005	7.244	93.7	86.456	14850.0
281055	6.678	93.7	87.022	14900.0
281105	6.27	93.7	87.43	14950.0
281155	6.115	93.7	87.585	15000.0

INDICATIVE DRAWING

NOTE:-
MINIMUM HEIGHT OF EMBANKMENT SHALL BE PROVIDED AS PER RELEVANT PARA OF PART II OF BID DOCUMENT.

LEGEND

EXIST. IR TRACK	
PROP. DFCC TRACK	
EXIST. LAND BOUNDARY	
DFC LAND BOUNDARY	
PROPOSED BRIDGE	
PROP. STRUCTURE	
EXIST. STRUCTURE	
RIVER/NALA	
WELL	
TREE/TREE CLUSTER	
COMPOUND WALL	
WORK TO BE DISMANTLED	
HIGH TENSION LINE	
POND	
TELEPHONE POLE	
ELECTRIC LINE	
OHE TOWER	
HAND PUMP	
GPS PILLAR	
RAILWAY SIGNAL	
OHE MAST	
RELIGIOUS STRUCTURE	
IOC PIPE LINE CORRIDOR	
ROAD	

DEDICATED FREIGHT CORRIDOR CORPORATION OF INDIA LTD.
(A GOVERNMENT OF INDIA ENTERPRISE)

EASTERN CORRIDOR

PROJECT: NEW KARCHANA TO NEW BHAUPUR(EASTERN CORRIDOR)
From Ch 278155 to Ch 507693

CONTRACT PACKAGE - 202

TITLE: PLAN AND PROFILE (Ch 276155 to Ch 281155)

SCALE: HORZ. 1:5000 VER. 1:500

DRAWING NO.: MON/RAIL/ALD

SURVEYORS AND CONTRACTORS Pvt. Ltd.
MONARCH

GENERAL CONSULTANT
AECOM Asia Co. Ltd.
AECOM
8TH FLOOR, INFINITY TOWER C DLF CYBER CITY
DLF PHASE II GURGAON 122002, INDIA