PROJECT SHEET NO. 83

INDICATIVE DRAWING

NOTE:-
MINIMUM HEIGHT OF EMBANKMENT SHALL BE PROVIDED AS PER RELEVANT PARA OF PART II OF BID DOCUMENT.

CHAINAGE (M)	REVISED CHAINAGE (M)	CUT/FILL (M)	FORMATION LEVEL (M)	GROUND LEVEL (M)
0.0	364072.868	1.225	105.782	105.554
50.0	364122.868	0.649	106.905	106.256
100.0	364172.868	1.975	107.019	105.044
150.0	364222.868	2.412	107.132	104.72
200.0	364272.868	2.656	107.245	104.589
250.0	364322.868	2.723	107.358	104.635
300.0	364372.868	2.681	107.472	104.791
350.0	364422.868	2.878	107.585	104.707
400.0	364472.868	3.015	107.623	104.608
450.0	364522.868	3.057	107.661	104.603
500.0	364572.868	3.112	107.698	104.586
550.0	364622.868	3.195	107.736	104.541
600.0	364672.868	2.964	107.774	104.81
650.0	364722.868	3.053	107.811	104.758
700.0	364772.868	3.143	107.849	104.706
750.0	364822.868	3.233	107.887	104.654
800.0	364872.868	3.257	107.925	104.668
850.0	364922.868	3.121	107.962	104.841
900.0	364972.868	2.936	108.0	105.064
950.0	365022.868	2.723	108.188	105.465
1000.0	365072.868	2.637	108.377	105.739
1050.0	365122.868	2.709	108.566	105.856
1100.0	365172.868	3.108	108.753	105.646
1150.0	365222.868	3.585	108.941	105.356
1200.0	365272.868	3.397	109.129	105.732
1250.0	365322.868	3.185	109.318	106.133
1300.0	365372.868	3.393	109.506	106.113
1350.0	365422.868	3.6	109.694	106.094
1400.0	365472.868	3.762	109.882	106.12
1450.0	365522.868	3.883	110.071	106.188
1500.0	365572.868	4.021	110.259	106.238
1550.0	365622.868	4.337	110.447	106.11
1600.0	365672.868	4.73	110.635	105.905
1650.0	365722.868	5.046	110.824	105.778
1700.0	365772.868	5.139	111.012	105.873
1750.0	365822.868	5.274	111.2	105.926
1800.0	365872.868	5.236	111.187	105.931
1850.0	365922.868	5.197	111.133	105.936
1900.0	365972.868	5.159	111.1	105.941
1950.0	366022.868	5.095	111.067	105.972
2000.0	366072.868	5.021	111.033	106.012
2050.0	366122.868	5.081	111.0	105.919
2100.0	366172.868	5.148	110.967	105.819
2150.0	366222.868	5.26	110.933	105.673
2200.0	366272.868	5.376	110.9	105.524
2250.0	366322.868	5.453	110.7	105.247
2300.0	366372.868	5.631	110.5	104.869
2350.0	366422.868	5.797	110.3	104.503
2400.0	366472.868	5.951	110.1	104.149
2450.0	366522.868	5.741	109.9	104.159
2500.0	366572.868	5.452	109.7	104.248
2550.0	366622.868	5.927	109.5	103.573
2600.0	366672.868	6.215	109.3	103.085
2650.0	366722.868	5.457	109.1	103.643
2700.0	366772.868	4.958	108.9	103.942
2750.0	366822.868	4.946	108.7	103.754
2800.0	366872.868	4.888	108.5	103.612
2850.0	366922.868	5.129	108.3	103.171
2900.0	366972.868	4.462	108.1	103.638
2950.0	367022.868	3.794	107.9	104.106
3000.0	367072.868	3.224	107.7	104.466
3050.0	367122.868	2.747	107.5	104.753
3100.0	367172.868	2.609	107.65	105.041
3150.0	367222.868	2.626	107.8	105.174
3200.0	367272.868	2.644	107.95	105.306
3250.0	367322.868	2.675	108.1	105.425
3300.0	367372.868	2.709	108.25	105.541
3350.0	367422.868	2.743	108.4	105.657
3400.0	367472.868	2.778	108.55	105.772
3450.0	367522.868	2.736	108.7	105.964
3500.0	367572.868	2.681	108.85	106.169
3550.0	367622.868	2.626	109.0	106.374
3600.0	367672.868	2.574	109.15	106.574
3650.0	367722.868	2.522	109.3	106.778
3700.0	367772.868	2.379	109.45	106.672
3750.0	367822.868	2.309	109.6	106.291
3800.0	367872.868	2.023	109.75	106.727
3850.0	367922.868	3.009	109.9	106.891
3900.0	367972.868	2.253	110.05	107.797
3950.0	368022.868	2.816	110.2	107.384
4000.0	368072.868	2.311	110.35	108.039
4050.0	368122.868	2.47	110.5	108.03
4100.0	368172.868	2.503	110.65	108.147
4150.0	368222.868	2.485	110.8	108.315
4200.0	368272.868	2.412	110.95	108.538
4250.0	368322.868	2.438	111.1	108.662
4300.0	368372.868	2.536	111.25	108.714
4350.0	368422.868	2.579	111.4	108.821
4400.0	368472.868		111.55	108.971
4450.0	368522.868		111.7	109.116
4500.0	368572.868		111.85	109.266
4510.472	368583.340		111.882	109.312

LONGITUDINAL SECTION

LEGEND

EXIST. IR TRACK	
PROP. DFCC TRACK	
EXIST. LAND BOUNDARY	EXIST. IR ROW
DFC LAND BOUNDARY	DFC DFC
PROPOSED BRIDGE	
PROP. STRUCTURE	
EXIST. STRUCTURE	
RIVER/NALA	
WELL	
TREE/TREE CLUSTER	
COMPOUND WALL	
WORK TO BE DISMANTLED	
HIGH TENSION LINE	
POND	
TELEPHONE POLE	T T
ELECTRIC LINE	T T
OHE TOWER	
HAND PUMP	
GPS PILLAR	
RAILWAY SIGNAL	
OHE MAST	
RELIGIOUS STRUCTURE	
IOC PIPE LINE CORRIDOR	IOC PIPE LINE IOC PIPE LINE
ROAD	

DEDICATED FREIGHT CORRIDOR CORPORATION OF INDIA LTD.
(A GOVERNMENT OF INDIA ENTERPRISE)

EASTERN CORRIDOR

PROJECT: NEW KARCHANA TO NEW BHAUPUR(EASTERN CORRIDOR)
From Ch 278155 to Ch 507693

CONTRACT PACKAGE - 202

TITLE: PLAN AND PROFILE (Ch 364072.868 to Ch 368583.340)

SCALE: HORI. 1:5000 VER. 1:500

DRAWING NO.: MON/RAIL/MTC

SURVEYORS AND CONTRACTORS Pvt.Ltd.
MONARCH
17, PANNALAL PLAT NO. 2, MUKTA APARTMENT
PREM NAGAR(NAI BALI), BIRPURA (NAU)
PUNE - 411 009

GENERAL CONSULTANT
AECOM Asia Co. Ltd.
AECOM
9TH FLOOR, INFINITY TOWER C DLF CYBER CITY
DLF PHASE II GURGAON 122002, INDIA