



e-Tender No. BRC/EN/ROB/LC-154 Date 15.03.2017

For

Construction of Road Over Bridge in lieu of existing LC No.154 At Rly km 283/10-12 (DFCC Ch : 33885.151 of Section-4 of DFCC) between station Sayan and KIM of BCT-ADI W.Rly Route & (JNPT(Mumbai) – Dadri (Delhi)- WDFC route.

FINANCIAL BID (PACKET-B)

**TENDER DOCUMENT
March, 2017**

**Employer:
CHIEF PROJECT MANAGER/VADODARA
DEDICATED FREIGHT CORRIDOR CORPORATION OF INDIA LIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)
Under
MINISTRY OF RAILWAYS**

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL



DEDICATED FREIGHT CORRIDOR CORPORATION OF INDIA LTD
 A Govt. of India (Ministry of railways) Enterprises
 4th Floor, Narmada Naher Bhavan, Near Chhani Jakat Naka, Vadodara-390002
NOTICE FOR INVITING BIDS (Online i.e. E-Tender)

Tender No	Vadodara/EN/ROB/LC – 154, date 15.03.2017
Name of work	Construction of Road Over Bridge in lieu of existing LC No.154 At Rly km 283/10-12 (DFCC Ch: 33885.151 of Section-4 of DFCC) between station Sayan and KIM of BCT-ADI W.Rly Route & (JNPT (Mumbai) – Dadri (Delhi)- WDFC route.
(a) Type of Tender	Open Tender (Single stage two packet).
(b) Type of Contract	Works Contract.
(c) Tender Value	Rs. 26,74,81,366/-
(d) Completion Period	18 months
(e) Earnest Money	Rs. 40,12,221/- (Paid through Demand Draft/ banker’s Cheque, FDR payable in favour of “ Dedicated freight Corridor corporation of India Limited, Vadodara”)
(f) Cost of Tender document	Rs 10000/- To be paid by D.D./Banker’s Cheque in favour of DFCCIL payable at Vadodara
(g) Tender Processing Fee	Rs7,500/- plus taxes and duties as applicable (non refundable) through e-payment while uploading of tender
(h) Performance Bank Guarantee	Performance Guarantee (PG) have to be submitted within 30(thirty) 15 (Fifteen) days from the date of issue of Letter Of Acceptance (LOA), amounting to 5% of the contract value in the form as give in clause 16.4 of GCC
(i) Retention Money / Security Deposit	5% of Contract Value
(j) Officer:	Chief Project Manager/ Vadodara, Dedicated Freight Corridor Corporation of India Limited 4th floor, Block-A, Narmada Naher Bhavan (Sardar Sarovar Narmada Nigam Ltd. Office), Chhani Jakat Naka, Vadodara, Pin . 390002, Gujarat.

Signature of Tenderer(s)
 Date:

For CPM/VADODARA/DFCCIL

(k) E-Tendering Web Site	E-tendering site- www.tenderwizard.com/DFCCIL Help: Please contact Tender wizard helpdesk at 011-49424365
(L)Pre bidding Conference	On 21.04.2017 at 15.30 Hrs at office of Chief Project Manager/ Vadodara, Dedicated Freight Corridor Corporation of India Limited 4th floor, Block-A, Narmada Naher Bhavan (Sardar Sarovar Narmada Nigam Ltd. Office), Chhani Jakat Naka, Vadodara, Pin . 390002, Gujarat.
DATE & TIME SCHEDULE	
Date of Uploading of NIT (Online Publishing date)	15.03.2017 at 11.00 Hrs.
Documents download/Sell date (Online)	From 01.04.2017 at 11.00 Hrs. To 12.05.2017 at 13.00 Hrs.
Bid submission Last date (Online)	12.05.2017 up to 15.00 Hrs.
Last date of submission of originals of statutory documents i.e. EMD & Tender Document Charge	23.05.2017 up to 13.00 Hrs.
Bid Opening date & Time (online)	23.05.2017 at 15.00 Hrs.

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

SUMMARY OF PRICES

Name of work: Construction of Road Over Bridge in lieu of existing LC No.154 At Rly km 283/10-12 (DFCC Ch : 33885.151 of Section-4 of DFCC) between station Sayan and KIM of BCT-ADI W.Rly Route & (JNPT(Mumbai) – Dadri (Delhi)- WDFC route.

Sl. No.	Description of Works	Cost as per schedules	Rates to be quoted in figures & words (Clearly mention above / below / at par on Schedules/Items updated DFCCIL Rate / cost given in column 3)
1	2	3	4
1	Execution of all works as per Schedule "A" (Items as per SOR 2015- 16 of State Govt. Gujarat R&B Surat division.)	2,35,47,547.00	Rates above / below / at par as per schedules shall be filled separately in Microsoft Excel File.
2	Execution of all works as per Schedule "B" (NS Items as per State Govt of Gujarat)	11,00,21,583.00	Rates above / below / at par as per schedules shall be filled separately in Microsoft Excel File.
3	Execution of all works as per Schedule "C" (Items as per SOR 2015- 16 of State Govt. Gujarat R&B Surat division.)	8,79,45,005.00	Rates above / below / at par as per schedules shall be filled separately in Microsoft Excel File.
4	Execution of all works as per Schedule "D"(NS Items as per Western Railway)	4,28,60,669.00	Rates above / below / at par as per schedules shall be filled separately in Microsoft Excel File.
5	Execution of all works as per Schedule "E"(NS Items as per Western Railway)	8,19,363.00	Rates above / below / at par as per schedules shall be filled separately in Microsoft Excel File.
6	Execution of all works as per Schedule "F"(NS Items as per Western Railway)	22,87,199.00	Rates above / below / at par as per schedules shall be filled separately in Microsoft Excel File.
	Grand Total	26,74,81,366.00	

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

Notes:

- (i) The above prices are inclusive of all taxes, duties including Excise duty, Sales Tax, Octroi, Local levies, Works Contract Tax etc.
- (ii) The tenderer should quote single percentage above / par / below for each schedule.
- (iii) If the uniform percentage quoted by the Tenderer does not clearly indicate whether the rates are above/at par/below the estimated rates then through sign convention it will be considered to be on plus side and evaluated accordingly.
- (iv) Rate of item payable to contractor shall be as per above/below/at par on rates of schedule.

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

SCHEDULE -1**SCHEDULE OF PRICES & TOTAL PRICES**

NAME OF WORK: Construction of Road Over Bridge in lieu of existing LC No.154 At Rly km 283/10-12 (DFCC Ch : 33885.151 of Section-4 of DFCC) between station Sayan and KIM of BCT-ADI W.Rly Route & (JNPT(Mumbai) – Dadri (Delhi)- WDFC route.

Schedule- A**Schedule of Approximate quantities**

S.N.	Item NO.	Total Quantity	Item of Work	Rate	Unit	Amount in Rs.
1	27007A	9147	Excavation for foundation in sand, gravel, clay soft soils and murrum etc. Including shoring, strutting dewatering as necessary and disposing of the excavated stuff as directed.	318.15	Cum	2910118.05
2	DSR 2014 Item 2.33		Felling trees of the girth (measured at a height of 1 m above ground (level), Including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material. Beyond			
2 (i)		2	30cm girth upto & including 60cm girth	198.67	Each	397.334
2 (ii)		2	60cm girth upto & including 120cm girth	879.81	Each	1759.622
2 (iii)		2	120cm girth upto & including 240cm girth	4069.34	Each	8138.681
3	27039	3321	Empty boring through all sorts of strata for providing 1.20m dia RCC bored piles to required depth including flushing necessary casting pipe with all plants and equipments as required as per detailed specifications for Abutment and Piers (Excluding Concrete & Reinforcement).	3361.28	Rmt	11162810.88
4	14023	2996	Providing and fixing pre-cast concrete kerb stone of gray cement based concrete block 30cm length,30cm height and 15cm thick of M250 grade concrete as per approved design and including excavation for fixing in proper line and level, filling the	239.37	Rmt	717152.52

Signature of Tenderer(s)

Date:

For CPM/VADODARA/DFCCIL

VADODARA/EN/ROB/LC-154, Date 15.03.2017

			joint with C:M 1:3 (1cement:3 fine sand) etc. complete.			
5	27001A	142.4	Chipping and dressing of the RCC piles up to cut off level (min 1 D) including cleaning of reinforcement and removal of dismantled materials etc for providing pile caps as directed by Engineer and as per specification for 1000 mm & 1200 mm.	577.72	Cu m	82267.328
6	26161	886.7 9	Road marking with hot applied thermoplastic compound with reflectorising glass beads on road surface providing and laying hot applied thermoplastic compound 2.5 CM thick including reflectorising glass bends @ 250 gms /sq mt area thickness of surface applied glassbend as per IRC -35 the finished surface to be level uniform and free from streaks and holes.	298.96	Sq m	265114.7384
7	26163	892	Supplying and fixing cat eye (stimsonite) made out from Acrlic strene- acrylonitrile of high impact polysterene fitted with moulded of methacrylate reflector cube corner reflector design filled with tightly adhering potting compound as per ASTM D-788 size 11.5 x 7 x 1.60 cm.	375.72	Eac h	335142.24
8	27050A	0	Providing and laying weep hole in abutments, and returns by using AC pipe of 100 mm dia. Including laying in proper grade and jointing the completed as per detailed specification.	53.93	Eac h	0
9	27072	1935 275	Providing and Fixing in position fully moulded restrained elastomeric bearings as per detailed drawings.	1.11	Cu m	2150101.635
10	27101A	2	Providing and fixing marble slab including engraving and painting complete.(A) size 75 cm x 60 cm x 4 cm	955.46	No.	1910.92
11	27098A	41	Providing, fabricating and fixing in position GI Drainage Spout arrangements having 100 mm dia. Pipe B class with necessary bend, fixing to GI chamber, GI grating, providing and applying one coat of primer & two coat of anticorrosive paint, etc. complete as per drawing and as per specifications.	506.01	No.	20746.41
12	M664	200	providing and fixing 100 dia runner and downtake GI pipe to drain water from drainage spout with necessary fixtures including cost of all materials, labours,	808.00	RM T	161600

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

VADODARA/EN/ROB/LC-154, Date 15.03.2017

			bends, fixtures, specials ec. Complete as per drawing and Sp. And as per direction of engineer.			
13	26008	4534	Box cutting the road surface to proper slope and camber for making a base for road work including removing the excavated stuff and depositing on the road side slope as directed upto 50 mt lead.	66.16	cu m	299946.77
14	26B004 E	5489. 88	Earth work for embankment including breaking clods dressing with all lead and lift and including watering, rolling and consolidation of subgrade in layers at O.M.C. to required dry density including filling depressing which occur during process using vibratory roller 8 T to 10T (from borrow area within 5km lead)	243.4	Cu m	1336291.691
15	26048	4	providing & fixing ordinary Kilometre stone of precast C.C. 1:2:4 including necessary reinforcement as per I.R.C. type design in C.C. 1:4:8 including letter & paints etc. complete (For N.H., S.H. & M.D.R.)	842.34	Eac h	3369.36
16	26089E A	20	Supplying and fixing reinforced concrete heavy duty non pressure pipes with collors for culverts carrying heavy traffic as per IS 458-1991 specifications including setting the pipes in C.M. 1:2 watering and laying (to level slopes) of class NP3 of internal diameters (v) 900mm dia (more then 10 ton)	2097.77	Rm t	41955.4
17	26101B	4	Providing and fixing village name boards made from 2mm aluminium sheet; size 90x 60cms. rectangle as per the design of IRC-67-2015 pretreated with phosphating process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint; reflectorized with retro reflective sheeting as per latest MOST Specifications; 3.1m long (2 Nos) stand post and frame fabricated from suitable size iron angle of 50 x 50 x 5mm; painted with best quality epoxy coatings in black and white bends. the details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x60cms. for each leg. including excavation curing etc. complete under the supervision of engineer (B) High intensity	4163.22	No.	16652.88

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

			Grade			
18	26092A	2	Providing and fixing Cautionary Sign Board made out of 2mm aluminium sheet, size 90 x 90 x 90 cms equilateral triangle, as per the design of IRC-67-2015. Pre treated with phosphating process and acid etching coated with one coat of epoxy primer and two coats of best quality epoxy paint, reflectorized with retro reflective sheeting as per the latest M.O.S.T. specification, 3.1 Mt. long stand post and frame fabricated from suitable size iron angle of 35 x 35 x 3 mm, 75 x 75 x 6 mm; painted with best quality epoxy coating in black and white bends. The details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 cms for each leg, including excavation curing etc. complete under the supervision of Engineer-In-Charge (A) Engineer grade.	3182.51	No.	6365.02
19	26092B	4	Providing and fixing Cautionary Sign Board made out of 2mm aluminium sheet, size 90 x 90 x 90 cms equilateral triangle, as per the design of IRC-67-2015. Pre treated with phosphating process and acid etching coated with one coat of epoxy primer and two coats of best quality epoxy paint, reflectorized with retro reflective sheeting as per the latest M.O.S.T. specification, 3.1 Mt. long stand post and frame fabricated from suitable size iron angle of 35 x 35 x 3 mm, 75 x 75 x 6 mm; painted with best quality epoxy coating in black and white bends. The details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 cms for each leg, including excavation curing etc. complete under the supervision of Engineer-In-Charge (B) High Intesity grade.	3272.40	No.	13089.6
20	26103B	8	Providing and fixing sign boards made from 2mm aluminium sheet; size 100x 100cms. as per the design given by engineer in charge pretreated with phosphating process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy	6618.53	No.	52948.24

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

			paint; reflectorized with retro reflective sheeting as per latest MOST Specifications; 3.1m long (2 Nos) stand post and frame fabricated from suitable size iron angle of 35 x 35 x 3mm & 50 x 50 x 5mm 75 x 75 x 6mm ; painted with best quality epoxy coatings in black and white bends. the details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60cms. for each leg. including excavation curing etc. complete under the supervision of engineer (B) High intensity Grade			
21	26098A	2	Providing and fixing Junction Board made out of 2mm aluminium sheet, size 244 x 122 cms rectangle, as per the design of IRC-67-2015. Pre treated with phosphating process and acid etching coated with one coat of epoxy primer and two coats of best quality epoxy paint, reflectorized with retro reflective sheeting as per the latest M.O.S.T. specification, Letters and numerals should be as per IRC-30-1968. 3.1 Mt. long (2 nos.) stand post and frame fabricated from suitable size iron angle of 50 x 50 x 5 mm, 75 x 75 x 6 mm; painted with best quality epoxy coating in black and white bends. The details of symbol or inscription/ numerals for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 cms for each leg, including excavation curing etc. complete under the supervision of Engineer-In-Charge (A) Engineer grade.	12274.53	No.	24549.06
22	14006A	127	Providing and laying chequered terrazo tiles 22mm thick for R.C.C Staircase with marble chips of size upto 6mm in floors on 25mm thick bed of lime mortar 1:1.5 (1 - lime putty : 1.5 coarse sand) or C.M. 1:6 jointed with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing & polishing complete. (A) Light shades using white cement.	475.71	Sq m	60415.17
23	M942	81.53	Providing and fixing 50 mm Dia UPVC pipe for entry cable pipe.	133.32	Rm †	10869.5796
24	27100A	136	Providing PVC 100 mm diameter water	187.86	Eac	25548.96

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

			spouts including necessary iron grating as per drawing.		h	
25	26117 C	1.8	Clearing and grubbing site/road/land including uprooting all vegetation, grass, bush shrubs, saplings and trees with girth, removal of stumps of trees of girth of all sizes including removing stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable materials as directed by Engineer with all leads and lifts etc. complete as per specification. before commencement and after completion of the work.	32056.39	LS	57701.502
26	27087	59	Providing Vertical Joints-pre moulded asphalt filler joints as per drawings (A) 12 mm	733.26	sq. m	43262.34
27	11012	372	Providing and fixing MS round holding down or Anchor bolts (J type) with nuts and washer plates complete.	40.00	kg	14878.512
28	11001A	2.91	Structural Steel :- Base plate of 220 x 220 x 12 mm thick with adjustment of hole. MS plate 6mm thick 20mm wide 150mm long including welding to the base plate all complete.	6027.68	Qui	17540.5488
29	23067	1287	Providing, laying and jointing in true line and level 110 diameter UPVC (Type B) conforming to IS 13592:1992 with one end plain and other end socketed with rubber ring & fitting conforming to IS 14735:1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with lubricant, pipe shall be fixed on wall using of PVC clamp of size 110 mm diameter x 149mm length x145mm height at every 2000 mm centre to centre or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all maerials	531.26	Rm †	683731.62
30	27097A	134	Providing and fixing post and pipe railing as per detailed drawing including 3 coats of painting to steel works complete.(more than 10 ton)	1073.63	Rm †	143866.42
31	NH SOR 8.8	2471. 18	Painting two coats after filling the surface with synthetic enamel paint in all shades on crash barrier concrete surfaces	63.63	Sq m	157241.0969

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

VADODARA/EN/ROB/LC-154, Date 15.03.2017

32	20003B	195	Demolition of brick work and stone masonry including stacking of serviceable materials and disposals of unserviceable materials with all lead and lift(ii) in cement mortar.	340.37	Cu m	66372.15
33	NH SOR 13.16	3900	Supplying, fitting , fixing in position true to line and level POT- PTFE bearing consisting of metal piston supported by a disc of unreinforced elastomer confined within a metal cylinder, sealing rings, dust seals, PTFE surface sliding against stainless steel mating surface, complete assembly to be cast steel/fabricated structural steel, metal and elastomer elements to be as per IRC:83 part I& II respectively and other parts conforming to BS:5400, section 9.1 & 9.2 and clause 2006of MORTH specifications complete as per drawing and apperoved Technical specification.	57.57		224523
34	NH SOR 14.1 G case(ii) q	362	providing and casting in situ controlled cement with pozolona slag cement of M50 for RCC work in superstructure including centering, shuttering, scaffolding, ramming, vibrating, curing and finishing complete.	6710.44	M.T	2429179.28
Total Amount of Schedule – A						2,35,47,547.45

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

Schedule B						
Schedule of Approximate quantities						
S.N.	Item NO.	Total Quantity	Item of Work	Rate	Unit	Amount in Rs.
1	NS/01	3	Marking out the center line of the Bridge and various other component structures and complete lining out and leveling with theodolite, levels, including constructing necessary masonry pillars for lines and levels and establishing necessary bench marks etc. complete as directed.	12625.00	LS	37875
2	NS/02	888	providing & filling in foundation with ordinary cement concrete M 15 mix and providing necessary vertical pin headers including formwork vibrating ramming & curing complete.	2622.6	Cu m	2328842.16
3	NS/03	3480	Providing and casting in situ controlled cement concrete M-35 for RCC bored pile from 1.20 m. dia. using Tremie Pipe including necessary flushing, dewatering, formwork, mixing in mechanised batch mix plant, transporting, compacting and finishing including all leads & lifts complete as per detailed specifications. (Excluding Reinforcement).	3947.1	Cu m	13735838.4
4	NS/04	1678	Providing and casting in-situ controlled cement concrete of M35 grade for RCC work for Pile cap ,pier, abutment,RCC Stair Case & retaining walls foundations with 20/40mm down coarse aggregate of the required size for any depth including dewatering, scaffolding centring, shuttering, mixing, placing in position, consolidating with mechanical vibrators, curing, deshuttering carefully, making good the damages, fixing embedment, inserts, pockets, wherever necessary as per specification and drawing.	3943.0	Cu m	6616421.12
5	NS/05	415.6	Providing and casting in situ controlled	4004.3	Cu	1664166.3

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

			cement M35 for RCC work in piers and abutment return wall as per drawing including centering shuttering scaffolding where necessary laying vibrating curing and finishing complete. A) height from 0.0 to 5.0 m		m	
6	NS/06	56.7	Providing and casting in situ controlled cement M35 for RCC work in piers and abutment return wall as per drawing including centering shuttering scaffolding where necessary laying vibrating curing and finishing complete. A) height from 5m to 10.0 m	4226.5	Cu m	239639.715
7	NS/07	933.9	providing and casting in situ controlled cement concrete M35 for RCC works on pier cap abutment cap and dirt wall including controlled cement concrete or pedestals of required drawings, centering shuttering, scaffolding wherever necessary laying vibrating curing and finishing complete.	4056.8	Cu m	3788617.503
8	NS/08	23	providing and casting in situ controlled cement concrete M35 for RCC works on pier cap abutment cap and dirt wall including controlled cement concrete or pedestals of required drawings, centering shuttering, scaffolding wherever necessary laying vibrating curing and finishing complete.	4537.1	cum	104353.76
9	NS/09	2580	Providing and casting in situ controlled cement concrete M-35 for R.C.C. work in superstructure including centering, shuttering scaffolding , ramming, vibrating curing and finishing complete. (A) T-Beam and Deck slab type of superstructure. (II) Main and cross Girder	4430.7	Cu m	11431128.6
10	NS/10	194	Providing and casting in-situ controlled cement concrete of M-35 grade with minimum cement content 420kg/cum without admixture as per IS-456-2000, reinforcement cement concrete with 20mm downgraded crushed stone aggregates of required size in super structure for approach slab including required formwork, shuttering and supporting arrangement (excluding cost of reinforcement) and transporting	4111.3	Cu m	797594.14

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

			concrete from batching plant by transit mixture placing it in position, compacting with needle vibrator including curing with all labour, material, machinery all lead, lift etc. complete as per drawing and technical specification of MORTH & as directed by Engineer Incharge.			
11	NS/11	1699	Providing and casting in -situ controlled cement concrete of M 40 grade for RCC crash Barrier with 20 mm down coarse aggregate of the required size including formwork, shuttering, placing in position, consolidation with mechanical vibrators curing finishing, deshuttering carefully, marking good the damages, fixing embedment, inserts, pockets, wherever necessary as directed and as per drawing with F3 type exposed concrete finish and formwork as directed by Engineer - in - charge, etc. complete as per specification.	4050.1	Cu m	6881119.9
12	NS/12	14570	PRIMER & PROTECTIVE COATING-providing and laying the external decoative waterproff & Protective coating system for concrete and masonry shall be MASTERSEAL 200H , a single component elastomeric crack bridging acrylic coating applied at an average thickness of 50 micro DFT in two coat the product shall be applied on ssuitability primed substate using MASTERSEAL 399 as primer . The product must be crack bridging elongation type with elongation at break , exceeding 200% & tensile strength exceeding 2 MPa The system shall exhibit exellant bond strength with the substrate at least exceeding 1.0 MPa , when tested as per ASTM D 4541.	182.8	Sqm	2663541.7
13	NS/13	185.6	Providing and fixing in position Strip Seal Type Expansion Joint (for movement upto 60mm) as per detailed drawing MORTH specification. The rate is inclusive of supplying, fixing with contractor's own materials, equipments, machineries, labour, transport, testing, bolts, socket tubes, neoprene sheet/cap etc. complete. The rate is finished item	9065.8	Rmt	1682605.056

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

			complete and will be paid after fixing in all respect.			
14	NS/14	0.12	Providing Pylon consist of cast-in-situ concrete of M30 grade exposed finish as per drawing and as directed by engineer in charge. Rate includes providing required shuttering and form work but excluding stone slab & carving. (Reinforcement shall be paid in respective item.)	3884.2	Cu m	466.0992
15	NS/15	4160	Reinforced Earth Retaining Wall (Reinforced Earth retaining wall is having following main component 1. Excavation for foundation, foundation concrete (CC grade M15) with cement concrete grooved seating in foundation for fascia panel. 2. fascia material and its placement 3. Assembling & joining with fascia elements and laying reinforcing element 4. earthfill with granular material which is to be retained on wall , fascia elements of RCC	5848.1	Sqm	24328179.2
16	NS/16	6291.95	Construction of 250 mm thick compacted coarsed granular subbase (Grade I crushed B.T. materials of 53 mm to 26.5 mm@ 35%, 26.5mm to 4.75mm @45% , below 2.36mm @20 %) by providing close graded material mixing in mechanical mix plant at OMC, carriage of mix material to work site, spreading uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve desired density complete clause as per 401	841.3	cum	5293606.294
17	NS/17	4811.91	Providing and laying wet mix base course macadam 250 mm in Two layer using machine crushed chips as per required gradation mixing with required optimum quantity of water conveying mix to site and spreading to grade and ccamber with mechanical paver consolidation by vibratory roller including material, labour, plant and machinery and equipment etc complete	915.1	Cu m	4403186.365
18	NS/18	21748.4	Providing and appying priming coat using medium setting emulsion bitumen as the rate of 7.5 kg/10 sq.m on WMM surface	20.8	Sqm	452584.204

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

VADODARA/EN/ROB/LC-154, Date 15.03.2017

			including cleaning the surface etc comp			
19	NS/19	3563	Providing and laying 100 mm thick DBM in two layers using crushed stone aggregate BT chips as per required gradation and using emulsion asphalt as a tack coat @ 2.5 kg/10sqmt and VG 30 grade asphalt at 45 kg/MT) by total weight of mix hot laid process using drum mix process transporting mix and laying by paver finisher including consolidation with vibratory roller including cost of material, labour, machinery equipment and fuel, oil, lubricant for plant and machinery using contractor's own plant and machines etc complete.	1982.6	M.T.	7064110.69
20	NS/20	1789	Providing and laying 40 mm bitumen concrete using crushed stone aggregate BT chips as per required gradation and using emulsion asphalt as a tack coat @ 2.5 kg/10sqmt and VG 30 grade asphalt at 55 kg/MT) by total weight of mix hot laid process using drum mix process transporting mix and laying by paver finisher including consolidation with vibratory roller including cost of material, labour, machinery equipment and fuel, oil, lubricant for plant and machinery using contractor's own plant and machines etc complete.	2195.7	M.T.	3928178.86
21	NS/21	0	providing and casting in situ controlled cement concrete M 30 mix for RCC works in retaining wall of required detailed drawing, centering shuttering, scaffolding wherever necessary laying vibrating curing and finishing complete.	3884.2	Cu m	0
22	NS/22	3727.56	Providing and laying 25 mm thick mastic asphalt wearing course with paving grade bitumen meeting the requirements given in table 500-29, prepared by using mastic cooker and laid to required level and slope after cleaning the surface, including providing antiskid surface with bitumen precoated finegrained hard stone chipping of 13.2 mm nominal size at the rate of 0.005cum per 10 sqm and at an approximate spacing of 10 cm center to center in both directions, pressed into	379.8	Sqm	1415578.186

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

VADODARA/EN/ROB/LC-154, Date 15.03.2017

			surface when the temperature of surfaces is not less than 1000C, protruding 1 mm to 4 mm over mastic surface, all complete as per clause 515.			
23	NS/23	17171	providing sand & filling in approach portion RE wall(as per MORTH section 3100) including laying of earth as per specification for compaction in 250 mm thick loose layers and dressing (MORTH specification Cl. By machanical means using motor grader including 305.3.5) watering the earth to bring the earth upto required OMC including rolling with the use of vibratory roller when earth is at suitable moisture content with desired field density not less than 97% of maximum dry density (modified proctor test). The material for filling shall conform to IRC Highway Research Board's special report No 16	615.1	Cu m	10561710.39
24	NS/24	6023	Providing & laying 37.5 mm thick compacted built up spreay grout base course in single layers for bringing the road surface in to camber and gradient over existig road surface with bitumen grade VG-30 for tack coat at the rate of 2.50 kg/10 sq.m of road surface area and using 0.50 cum stone aggregate per 10 sqm with asphalt for grouting @ 15 kg per 10 sqm of road surface and using 0.13 cmt of key aggregate per 10 sqm of road surface including heating and consolidation in both layers by vibratory roller as per MORTH specification clause no 506 including cost of all materials, fuel, labours, tools etc completed.	100.0	Sqm	602239.77
			Total Amount of Schedule – B			11,00,21,583.4

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

Schedule C						
Schedule of Approximate quantities						
S.N.	Item NO.	Total Quantity	Item of Work	Rate	Unit	Amount in Rs.
1	27020A	121.16	Providing and installing 6 mm MS liner for bored-cast-in-situ concrete piles including applying protective coating as per drawing and specification and as directed by Engineer.	51899.15	MT	6288101.377
2	27043C	522.4	Providing and fixing in position Fe 500 TMT for R.C.C bored pile as per detailed drawing including cutting, bending, hooking and tying and welding complete and including forming the cage and lowering it in position.(up to 10 ton)	44549.08	MT	23272439.39
3	27047A	240.7	Providing and fixing in position Fe steel bar reinforcement of steel bar reinforcement of steel grade Fe-500 TMT for R.C.C pile cap including cutting, bending, hooking and tying and welding etc., complete as per detailed drawing and specifications.	38606.24	MT	9292521.968
4	27109	215.56	Providing and fixing in position Fe steel bar reinforcement of steel bar reinforcement of steel grade Fe-500 TMT including cutting, bending, hooking and tying and welding etc., complete as per detailed drawing and specifications.(A) Abutment cap and Dirt wall (B)	45575.24	MT	9824198.734

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

VADODARA/EN/ROB/LC-154, Date 15.03.2017

			Abutment Pier & Retaing wall.			
5	27111	58	Providing and fixing in position Fe steel bar reinforcement of steel bar reinforcement of steel grade Fe-500 TMT including cutting, bending, hooking and tying and welding etc., complete as per detailed drawing and specifications.(A) Pier cap (B) Pedstals & Seismic arrester	45576.25	MT	2643422.5
6	27115	784.47	Providing and fixing in position Fe steel bar reinforcement of steel bar reinforcement of steel grade Fe-500 TMT including cutting, bending, hooking and tying and welding etc., complete as per detailed drawing and specifications.(B) T. Beam and slab type of (i) Deck slab superstructure. (ii) Main and cross girder.	44990.45	MT	35293658.31
7	27123	9.8	Providing and fixing in position steel bar reinforcement For Approach slab of steel grade FE-500 D (TMT) including cutting ,bending, hooking, tying, welding etc. complete as per detailed drawing and specification.	44298.60	MT	434126.28
8	NH SOR CH 14 Item No 14.3	6.14	High tensile steel wires / strands including all accessories for stressing, stressing all operations and grouting complete as per drawing and technical specification.	146015.70	cum	896536.398
			Total Amount of Schedule – C			87945004.96

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

Schedule D						
Schedule of Approximate quantities						
S.N.	Item NO.	Total Quantity	Item of Work	Rate	Unit	Amount in Rs.
1	NS/01	337	Supply & Fabrication of steel girder spans including its components (Stiffeners, Bracings, Splices, Studs etc.) as per the approved drawings for composite construction of superstructure of the Road Over Bridge with contractor's own Steel confirming to IS: 2062 Grade 250(B) with all welds, HSFG Bolts, nuts bolts, rivets etc. with contractor's own materials, fabrication, machinery, templates, fixtures, equipments tools and plants transportation, skilled/unskilled labour, excise duty., Octroi, sales tax and other taxes, all leads lifts, descent, loading, unloading, crossing one or more Railway track if required etc. complete and as per technical specifications. The rate is inclusive of transportation of fabricated girder parts to site by contractor's own means at his cost. The rate shall also be inclusive of cold straightening of deformed and bent girder parts before their assembly.(The Structural Steel to be used Should be manufactured by SAIL/RINL/TISCO/ESSAR/JINDAL Only.)Work has to be done as per drawings and specifications approved by DFCCIL/ Railway. High quality superior brand of paint should only be used. For Painting prior approval for superior brand / make of the paint should be taken from engineer in charge. Note:1. The	94629.73	MT	31890219.00

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

			<p>fabrication of girders must be got done from RDSO approved firms only.</p> <p>2. The rate is inclusive of assembly of girder with service bolts as per approved drawing in shop for checking by Engineer's representative and dismantling the same after checking for transportation to the site.</p> <p>3. Weight of HSFG bolts, Rivets, Welds shall not be considered for payment. Nominal weight of the girder spans including its components (Stiffeners, Bracings, Splices, Studs etc.) as per drawing will only be considered for payment.</p>			
2	NS/02	5335	<p>Metalizing girder / girder components such as cross girders, top chord channels, bracing etc. of Steel Girder as directed by Engineer with aluminium spray not less than two layers after preparing surface by sand/grit blasting as per provision laid in Appendix VI of IRS B 1179 code (latest alteration) including one coat wash primer (IS-5666) one coat zinc chrome primer (IS-104) and two coats of aluminium paint (IS-2339) with approved paint conforming to IS specification for fabrication & erection of steel girder bridge (RS B 1-79) as corrected up to date with contractor's own materials, tools, plants labour, loading/unloading, transportation, handling, re-handling if any including all lead, lifts descents, crossing of track/obstruction etc. complete in all respect and as per direction of the Engineer.</p>	607.09	Sqm	3238825.00
3	NS/03 NS/3A NS/3B		<p>Assembling, Welding, Erecting, Bolting by HSFG bolts, Riveting if any as per approved drawings and Launching of girder spans including its components on running line / Non- Running line /Running electrified line / under block period with the help of road crane of required capacity as per Railway's approved drawings & Scheme with other ancillary steel structures fixed to the girder, where necessary, in proper level and alignment and as per technical specifications. The rate</p>			

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

VADODARA/EN/ROB/LC-154, Date 15.03.2017

			shall be inclusive of supply, erection and dismantling of staging and scaffolding and other temporary arrangements required for the purpose of assembly, erection and launching of girders. The rate shall also be inclusive of cold straightening of deformed and bent girder parts before/after their assembly. Work has to be done as per drawings and specifications approved by Railway.			
			Note: Weight of HSFG bolts, Rivets, Welds shall not be considered for payment. Nominal weight of the girder spans including its components (Stiffeners, Bracings, Splices, Studs etc.) as per drawing will only be considered for payment.			
		337	Launching of Steel girder spans including its components on running line /Running electrified line / under block period with the help of road crane of required capacity as per Railway's approved drawings with other ancillary steel structures fixed to the girder where necessary in proper level and alignment and as per technical specifications.	16825.91	MT	5670332.00
		0	lanthing of steel girder span including its components on non-running line with the help of road crane of required capacity as per Railway's approved drawings with other ancillary steel structures fixed to the girder where necessary in proper level and alignment and as per technical specifications.	3181.19	MT	0.00
4	NS/04	20	Fabricating, supplying and erecting in position standard structural steel sections manufactured from IS approved manufacturers only ,conforming to IS :2062 - 1992 (including latest amendments) including welding with approved quality welding rods, supply and fixing of correct size turn bolts including one primer coat of red lead paint conforming to IS:102 or Zinc chromate paint conforming to IS:104 followed by tow coats of Aluminium paint as per IS : 2339 with all contractor's	71620.22	MT	1432404.00

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

VADODARA/EN/ROB/LC-154, Date 15.03.2017

			materials, labour, tools and plants etc in bolted/welded construction as directed by Engineer in charge. Work shall be carried out as per IS:800-1984 (with latest amendments), IRS specification No. B3-61 part 2 and IS 816 for welding.			
5	NS/05		Providing and fixing POT -PTFE bearing as per IRC 83 in position true to line and level including cost of all materials fixtures surface for receiving bearing, grouting of sleeves with non shrink high strength grout, load testing of bearing, transporing and fixing in position including all lead and lift etc. complete as per approved designs and drawing and as directed by Engineer.			
		2	NS/5a) Fixed bearing (Capacity upto 250 MT)	53550.00	No.	107100.00
		2	NS/5b) Sliding bearing (Capacity upto 250 MT)	53550.00	No.	107100.00
			Note: The rate is for finished item complete and paid only after fixing in position below the girder.			
6	NS/06	1	Load testing of one composite steel /Span Designing and Load testing of one composite girder/ Span as selected by the Engineer confirming to Rly. Standard's with loads to be applied and removed incrementally etc. complete as per special condodition and specification of contract, as per relevent IS/IRC codes with all contactors labour supervisor, T & P's all taxes, equipment, leading materials instruction of load test jacks etc., dial gauges, including all lead and lift.	256339.20	Each	256339.00
7	NS/07	132	Conducting Pile low strain integrity test as per ASTM D 5882- 96 code of American Society for Testing on cast - in situ RCC pile of 1200 mm diameter inclusive of analysis with all contractor's equipment, manpower, site preparation, lead and lifts etc. complete as per standard procedure, and as directed by the Engineer in charge. Note:- Rate is inclusive All equipment, All labour and consumable required & Mobilization of equipment	1199.62	Each	158350.00

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

			Total Amount of Schedule – D		4,28,60,669.00
--	--	--	-------------------------------------	--	-----------------------

Schedule E						
Schedule of Approximate quantities						
S.N.	Item NO.	Total Quantity	Item of Work	Rate	Unit	Amount in Rs.
1	NS/1	100000	Autocad Drawings : Preparation / Alternation and submission of drawings such as general arrangement drawings , phase drawings, scheme plan, structural drawings etd. On Auto Cad as per details and directions given by the Engineer in charge including plotting and submitting in standard inklet film of 50 micron and CD, submitting check prints on A3/A2/A0 size papers and final rint complete and as per insturctions of Engineer in charge.	0.4	Per Sqcm	40000.00
2	NS/2	1	Site Office Providing, arranging, managing and maintaining 500 sq.ft. well furnished AC office and well equipped Laboratory with 3 tables, 10 chairs, 2 steel almira, one computer with printer & operator, sufficient number of display etc. to the satisfaction of the Project Manager including Electrical, Water expenses etc. For execution of this item the date of start shall be considered only when the Contractor has actually rented/constructed the required premises established the office & Laboratory as per requirement. This item shall remain valid only for original contact period; no additional payment shall be made for whatsoever reason even if time extension is provided or date of	500000	LM	500000.00

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

VADODARA/EN/ROB/LC-154, Date 15.03.2017

			completion is extended. This office and laboratory including furniture and all other equipment shall be property of contractor after completion of Project.			
3	NS/3	191	Providing & fixing Safety Screen as per RDSO Drg. No. EL / C / 0068 MOD " E " , on the Parapet with necessary fixtures etc. as per detailed drawing including contractor's own materials, labours, tools and plants, etc. complete.	1179.8	Sqm	225342.00
4	NS/4	4	Making and supplying of check rails of 52 kg/ 60 kg rails of various lengths for level crossing as per approval drawings.	2997	Each LC	11988.00
5	NS/5	126.8	Providing, fixing and maintaining MS fabricated traffic barricading of 2.50m height on either side of the carriage way / portion of the carriage way closed to the traffic including provision of all sign boards/ bollards and warning lights etc. as per the Engineer in charge.	331.49	Meter	42033.00
			Total Amount of Schedule – E			819363.00

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

Schedule F						
Schedule of Approximate quantities						
S.N.	Item NO.	Total Quantity	Item of Work	Rate	Unit	Amount in Rs.
1	192100		Conducting load testing of a single pile Up to following capacity in accordance with IS 2911(Part IV) including installation of loading platform and preparation of pile head or construction of test cap and dismantling of test cap after test etc with all labour, material, tool & plants, equipment, machinery, etc complete as per drawing and specification, as directed by the Engineer.			
1 (i)	192103	2	Initial load test above 100 ton capacity Up to 250 ton capacity pile. USSOR 2011 Western Railway Item no. 192103	199722.83	Each	399446
1 (ii)	192104	30	Extra for every increase of 50 T in pile capacity or part thereof over 250 T. USSOR 2011 Western Railway Item no. 192104	44255.77	Each	1327673
1 (iii)	192107	2	Routine Load Test above 100 ton capacity Up to 250 ton capacity pile. USSOR 2011 Western Railway Item no. 192107	280040.14	Each	560080
			Total Amount of Schedule – F			22,87,199.00
Total of Schedule A, B, C, D, E, F				Rs. 26,74,81,366.00		

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL

END OF TENDER DOCUMENTS

Signature of Tenderer(s)
Date:

For CPM/VADODARA/DFCCIL