



Tender No. MGS/07/2018-2019/4-ROB/02

for

Name of work:-Construction of Railway Spans and adjacent Viaduct Spans of 04 Nos. ROBs (excluding approaches) in lieu of level crossing No. 36/C/T at IR Chainage 559/15-17 between Pahleja-Karwandia, No. 74/C/E at IR Chainage 651/17-19 between Saidraja-Chandauli Majhwar, No. 76/C/E at IR Chainage 656/9-11 between Saidraja-Chandauli Majhwar and No. 83/B/T at IR Chainage 669/21-23 between Fly Over Cabin - Junction Cabin Mughalsarai Yard of Mughalsarai division of East Central Railway

**FINANCIAL BID
(PACKET-B)**

**Employer:
DEDICATED FREIGHT CORRIDOR CORPORATION OF INDIA LIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)
Under
MINISTRY OF RAILWAYS**

VSK yadav

GENERAL INFORMATION / DATA SHEET

TENDER NOTICE NO	MGS/07/2018-19/4-ROB/02 Dated 24.05.2018
Name of the work	Construction of Railway Spans and adjacent Viaduct Spans of 05 Nos. ROBs (excluding approaches) in lieu of level crossing No. 70/C/E at IR Chainage 644/5-7 between Karmnasa-Saidraja, No. 71/C/E at IR Chainage 645/9-11 between Karmnasa-Saidraja, No. 75/C/T at IR Chainage 653/19-21 between Saidraja-Chandauli Majhwar, No. 78/C/E at IR Chainage 661/19-21 between Chandauli Majhwar- Ganjkhwaja and No. 81/C/T at IR Chainage 667/35-37 between Ganjkhwaja-Mughalsarai of Mughalsarai division of East Central Railway
(a) Tender Value (in Rs.)	₹ 598,155,634.24
(b) Completion Period	18 months
(c) Earnest Money	₹ 5,981,556
(d) Date and Time of Issue of Tender	From 11 Hrs of 01.06.2018
(e) Last date and Time of submission of Tender	03.07.2018 upto 15:00 hrs
(f) Date and Time of Opening of Tender (Technical bids -Packet A)	On 03.07.2018 at 15:30 hrs Opening date of Financial Bid will be Notified later
(g) Validity of offer	120 days
(h) Retention Money / Security Deposit	5 % of Contract Value
(i) Performance Bank Guarantee	Performance Guarantee (PG) have to submit within 30(thirty) days from the date of issue of Letter Of Acceptance (LOA), amounting to 5% of the contract value in the form as give in clause 16.4 of GCC

Vak Yadav

SUMMARY OF PRICES


Name of work:- Construction of Railway Spans and adjacent Viaduct Spans of 04 Nos. ROBs (excluding approaches) in lieu of level crossing No. 36/C/T at IR Chainage 559/15-17 between Pahleja-Karwandia, No. 74/C/E at IR Chainage 651/17-19 between Saidraja-Chandauli Majhwar, No. 76/C/E at IR Chainage 656/9-11 between Saidraja-Chandauli Majhwar and No. 83/B/T at IR Chainage 669/21-23 between Fly Over Cabin - Junction Cabin Mughalsarai Yard of Mughalsarai division of East Central Railway

S. No.	Description of works	Cost as per USSOR 2012 of EC Rly / Basic Cost	DFCCIL updated %	DFCCIL updated cost in Rs	Rates to be quoted as Percentage above / below / at par on updated DFCCIL Rate / cost given in Column-5)
1	2	3	4	5	6
1	Execution of all works as per Schedule "A" (NS Item)	253,011,411.91	0	253,011,411.91	For each Schedule, Rates to be quoted in the Excel Sheet provided in the Financial Bid clearly mentioning Percentage above / below / at par on updated DFCCIL Rate / cost given in Column-5. The submission shall be online on the tenderwizad site. No physical submission of Financial Offer is required.
2	Execution of all works as per Schedule "B-I" (Items as per SOR 2012 of EC Rly Chapter -1 only)	51,390.00	20.28	61,811.89	
3	Execution of all works as per Schedule "B-II" (Items as per SOR 2012 of EC Rly Chapters - 3,4,9,11 & 18 only)	2,607,802.17	17.02	3,051,650.10	
4	Execution of all works as per Schedule "B-VI" (Items as per SOR 2012 of EC Rly Chapters - 19,20 & 22 only)	106,722,627.51	20.95	129,081,017.97	
5	Execution of all works as per Schedule "B-VII" (Items as per SOR 2012 of EC Rly Chapters - 21 only)	15,169,567.73	38.06	20,943,105.20	
6	Execution of all works as per Schedule "B-VIII" (Items as per SOR 2012 of EC Rly Chapters - 23 & 24 only)	2,318,747.95	24.46	2,885,913.69	
7	Execution of all works as per Schedule "B-XII" (Items as per SOR 2012 of EC Rly not covered by the items of Schedule -A ,Schedule-B-I,B- II,B-VI , B-VII ,B-VIII , C-I & C-II only)	5,000,000.00	17.02	5,851,000.00	
8	Execution of all works as per Schedule "C-I" (Cement- OPC 43 Grade)	36,121,017.92	9.35	39,498,333.10	
9	Execution of all works as per Schedule "C-II" (Reinforcement Steel FE 500D)	108,868,234.42	32.06	143,771,390.38	
	Grand Total			598,155,634.24	

VAKYADAV

NOTES:

- (i) The Tenderer shall quote single percentage for each Schedule. If the tenderer quotes different percentage (%) above / below againsts each items of any schedule (i.e. A, B-I, B-II, B-VI, B-VII, B-VIII, B-XII, C-I & C-II), else his offer will be summarily rejected.
- (ii) The above prices are inclusive of all taxes (GST, Works Contract Tax etc.), Octroi or Local levies
- (iii) If the uniform percentage quoted by the Tenderer does not clearly indicate whether the rates are above/at par/below the estimated rates then through sign convention it will be considered to be on plus side and evaluated accordingly.
- (iv) This Tender Schedule does not contain Schedules B-III, B-IV, B-V, B-IX, B-X and B-XI because of these Schedules are not present.
- (v) **Rate of item payable to Contractor shall be as per following example:-**
 - 1) For Schedule B-I (Updation factor is 1.2028, since 20.28% above is the rate of DFCCIL over USSOR 2012 of EC Railway). If the rate of any item of USSOR - 2012 of EC Railway/Schedule B-I is "X" and
 - a) If percentage quoted by the contractor is 5% above (+5%). Rate payable to contractor = $(X) \times 1.2028 \times 1.05$
 - b) If percentage quoted by the contractor is 5% below (-5%). Rate payable to contractor = $(X) \times 1.2028 \times 0.95$
 - c) If percentage quoted by the contractor is at par, Rate payable to contractor = $(X) \times 1.2028$
 - 2) Similarly updation factor for Schedule B-II, B-VI, B-VII, B-VIII, B-XII, C-I and C-II is 1.1702, 1.2095, 1.3806, 1.2446, 1.1702, 1.0935 and 1.3206 respectively.
 - 3) In case of NS items i.e. Schedule A, Updation factor shall be 1.



Name of work:-Construction of Railway Spans and adjacent Viaduct Spans of 04 Nos. ROBs (excluding approaches) in lieu of level crossing No. 36/C/T at IR Chainage 559/15-17 between Pahleja-Karwandia, No. 74/C/E at IR Chainage 651/17-19 between Saidraja-Chandauli Majhwar, No. 76/C/E at IR Chainage 656/9-11 between Saidraja-Chandauli Majhwar and No. 83/B/T at IR Chainage 669/21-23 between Fly Over Cabin - Junction Cabin Mughalsarai Yard of Mughalsarai division of East Central Railway

Sch-A-I Non Schedule Item

SN	NS Item	Description	unit	Qty	Rate	Amount	
1	NS-1	<p>Providing and laying in position machine batched, machine mixed and machine vibrated design Mix Cement concrete M-40 grade (cast in situ) Using 20 mm graded Crushed stone aggregate and coarse sand of approved quality in RCC deck slab laid to required camber including end cantilever, RCC crash barrier, RCC railing etc. including pumping of concrete to site of laying, finishing, using admixtures in recommended proportions (as per IS: 9103), if approved in mix design to accelerate or retard setting of concrete, improve Workability without impairing strength and durability with all contractor's labor, tools & plants material (excluding cost of cement reinforcement and suturing) Fuel consumables machinery, loading unloading, lead and lift complete in all respect as a complete jobs per speculations & as directed by engineer.</p> <p>Notes-</p> <p>(i) Payment for cement, reinforcement and shuttering shell be paid extra as per relevant USSOR item included in the relevant schedule.</p> <p>(ii) The concrete is to be poured at the approved safe height and distance from live OHE wires carrying 25KV AC traction (on IR Track) to cast monolithically to the required level as per approved drawing over already launched main steel girder with proper joining arrangement through shear connector.</p> <p>(iii) The necessary shuttering arrangement has to be planned. Using already launched main steel girder. No support from ground will be allowed for this purpose .The rates includes for working under running traffic condition, all leads, lifts, ascents, descents, all other obstructions etc</p> <p>(iv) The contractor shall make adequate arrangement below the girder to avoid falling of anything over the track during concreting of the slab. The rate includes design and provision of all temporary works and to ensure safety of running traffic at all times.</p>	1	CUM	1,682.11	8,510.05	14,314,840.21
2	NS-2	<p>Providing and laying in position machine batched. Machine mixed and machine vibrated Design mix cement concrete M-40 grade (Cast in situ) using 20 mm crushed stone aggregate and coarse and coarse sand of approved quality in wearing coat of lying. Finished using admixtures in recommended proportions (as per IS: 9103), if approved in mix design to accelerate or retard salting of concrete. Improve workability without impairing strength and durability with all contractors' labour, tools & plants, material (excluding cost of cement, reinforcement and shuttering) fuel ,consumables, machinery, loading, unloading, lead and lift complete in all respect as a complete job as per specification and as directed by engineer.</p> <p>Note-</p> <p>(i) Payment for cement, reinforcement and shuttering shall be paid extra as per relevant USSOR item included in the relevant schedule.</p>	1	CUM	609.67	4,584.95	2,795,306.47

W.K. Yadav

SN	NS Item	Description	unit		Qty	Rate	Amount
3	NS3	Supply, fabrication and erection of Welded type BOW STRING girders of required span BOW STRING girder of span more than 45.7 m as per RDSO standard drg / approved drawings, East Central Railway Unified Standard Specifications – 2012(amended up to date) and Indian Railways Standard specification for fabrication and erection of steel girder bridges and locomotive turntables (Fabrication Specification) Serial No B1- 2001 (amended up to date) including all incidental works etc, supplying and fixing in position of shop welding / shop bolting with nuts and washers, field bolts, STUD SHEAR CONNECTOR etc. required for complete fabrication of the girders and transportation of the fabricated materials at site and stacking of the same at places as directed by Engineer including metalizing as per clause No 39.2.1 of B1- 2001 over the structural members with all contractor's labour, fuel, consumables, machinery, loading, unloading, tools & plants, material, lead and lift complete job as per specifications and as directed by Engineer.	1	MT	330.00	127,739.63	42,154,077.90
		Notes					
		(i) Steel (Plates and Rolled section) should conform to IS: 2062-2011. It shall have Sub quality 'BO' & Grade E250 (Fe 410) for rolled sections and E350 (Fe 490) for plates shall be fully killed					
		(ii) The steel shall be procured only from those firms, which are Established, Reliable, Indigenous & Primary Producers of Steel, having Integrated Steel Plants (ISP), using iron ore as the basic					
		(iii)40% of rate payment shall be made after steel material required for fabrication (as per drawing) is received at site.					
		(iv)15% of rate payment shall be made on acceptance of fabricated components at site.					
		(v) 20% of rate payment shall be made after erection& launching.					
		(vi) (a) 10% of rate payment shall be made after metalizing/Painting (b)					
		(vii) No deduction for holes and no addition for rivets /bolts/welds etc shall be made.					
		(viii) The contractor shall submit the detailed erection drawing and launching scheme along with necessary design calculation for approval to DFCCIL before erection and launching of girder.					
		(ix) Temporary supports if any required for the erection/ launching shall be erected after the approval of Engineer. Nothing extra shall be payable on this account.					
		(x) The contractor shall take all safety precautions with Engineer as per extant rules/ guidelines Nothing extra shall be payable on this account					
		(xi) Notwithstanding above, the contractor shall be fully responsible for any mishap that may occur as a result of negligent working.Contractor has to take every precautionary measure for					
		(xii) The rate includes launching under traffic blocks wherever required. However, the rate does not include the cost of possession of traffic/ OHE block.					
		(xiii) The Block required shall be arranged by DFCCIL at the request of contractor. The duration of the block shall be as approved by Engineer. If the block granted is not made available					

WAKYADAV

SN	NS Item	Description	unit		Qty	Rate	Amount
		(xiv) However penalties, if any, levied by Indian Railways caused due to any careless working or otherwise of violation of the Terms and conditions of the track/ OHE block, shall be payable by the (xv) The cost of all tests as per prevailing code for acceptance shall be borne by contractor (xvi) The Rate also include fixing of 25 mm dia 200 long stud shear connectors as per Specification and drawing,					
4	NS4	Supply, fabrication and erection of Welded type Composite Plate girders of required span for IRC loading at site as per RDSO standard drg / approved drawings, Indian Railway Unified Standard Specifications - 2010 (amended up to date) and Indian Railways Standard specification for fabrication and erection of steel girder bridges and locomotive turntables (Fabrication Specification) Serial No B1- 2001 (amended up to date) including all incidental works etc, supplying and fixing in position of shop welding / shop bolting with nuts and washers, field bolts, STUD SHEAR CONNECTOR etc. required for complete fabrication of the girders and transportation of the fabricated materials at site and stacking of the same at places as directed by Engineer including metalizing as per clause No 39.2.1 of B1- 2001 over the structural members with all contractor's labour, fuel, consumables, machinery, loading, unloading, tools & plants, material, lead and lift complete job as per specifications and as directed by Engineer. NOTE :- Same as NS-3 from (i) to (xvi)		MT	1,588.91	119,865.19	190,454,999.04
5	NS5	Supplying fabrication & fixing in position BRC protection screen with MS angle frame, expanded metal (XPM),GI sheet of 16 gauge, j Bolts etc of approved Railway design with two coats of aluminium paints of approved manufacturer as per drawing no. RDSO/ETI/C/0068 with all contractor's labour, tools & plants, material, fuel, consumables, machinery, loading, unloading, lead & lift complete in all respect as a complete job as per specification & as directed by Engineer.	1	Kg	5,982.00	130.65	781,548.30
6	NS6	Erection of Prestressed Girder on bearings with crane at site on sub structure with labour, equipment, T&P and all temporary arrangements, scaffolding etc. complete with contractors design	1	Cum	1,320.00	1,902.00	2,510,640.00
		Sub-Total					253,011,411.91

AK Yadav

Name of work:-Construction of Railway Spans and adjacent Viaduct Spans of 04 Nos. ROBs (excluding approaches) in lieu of level crossing No. 36/C/T at IR Chainage 559/15-17 between Pahleja-Karwandia, No. 74/C/E at IR Chainage 651/17-19 between Saidraja-Chandauli Majhwar, No. 76/C/E at IR Chainage 656/9-11 between Saidraja-Chandauli Majhwar and No. 83/B/T at IR Chainage 669/21-23 between Fly Over Cabin - Junction Cabin Mughalsarai Yard of Mughalsarai division of East Central Railway

Sch-B-I

SN	USSOR-2012 ECR	Description	unit		Qty	Rate	Amount
1	014110	Providing and removing barricading with the help of portable fencing along the running track where the work is to be done in close vicinity of the track. Fencing shall consist of self supporting steel angles of size 50 x50x6mm, 1.5m long provided with hooks etc. and embedded in CC 1:2:4 block of size 0.23x0.23x0.23m placed at c/c distance of 2m along the track. 12mm dia rods in three horizontal layers tack welded with the angle posts including providing retro-reflective tapes in Horizontal & vertical direction. Note : Released material will be the property of the contractor after the completion of work. Cost of cement to be paid separately.	1	Meter	200	256.95	51,390.00
		Sub-Total					51,390.00

AK Yadav

Name of work:-Construction of Railway Spans and adjacent Viaduct Spans of 04 Nos. ROBs (excluding approaches) in lieu of level crossing No. 36/C/T at IR Chainage 559/15-17 between Pahleja-Karwandia, No. 74/C/E at IR Chainage 651/17-19 between Saidraja-Chandauli Majhwar, No. 76/C/E at IR Chainage 656/9-11 between Saidraja-Chandauli Majhwar and No. 83/B/T at IR Chainage 669/21-23 between Fly Over Cabin - Junction Cabin Mughalsarai Yard of Mughalsarai division of East Central Railway

Sch-B-II

SN	USSOR-2012ECR	Description	unit	Qty	Rate	Amount
1	031020	Providing and laying cement concrete, up to plinth in retaining walls, walls (any thickness) including attached plasters, columns, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets etc, excluding the cost of cement and of shuttering, centering.				
(a)	031023	1:2:4 (1 cement : 2 sand : 4 graded stone aggregate 20mm nominal size)	1 cum	50	2,911.03	145,551.50
2	094040	Precast Chequered factory made terrazzo tiles 22mm thick with graded marble chips size upto 6mm in floors jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing of cement slurry complete on 20mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand)				
(a)	094042	With ordinary cement with pigment	1 Sqm	312.48	653.47	204,196.31
3	042010	Centering and shuttering including strutting, propping etc. and removal of form for :				-
(a)	042011	Foundations, footings, bases of columns, raft foundation of washable aprons, Pile caps, Footings of FOB etc.	Sqm	153.60	138.30	21,242.88
(b)	042013	Suspended floors, roofs, landings, balconies, FOB slabs, walkway slabs and access platform	Sqm	459.44	230.28	105,799.84
(c)	042014	Lintels, beams, plinth beams, bed blocks, girders, bressumers and cantilevers	Sqm	938.88	201.54	189,221.88
(d)	042015	Columns, pillars, posts and struts	Sqm	1503.36	282.30	424,398.53
(e)	042016	Stairs (excluding landings) except spiral-staircases	Sqm	220.96	391.60	86,527.94
4	041010	Providing and laying in position M-20 Grade concrete for reinforced concrete structural elements, but excluding cost of centering, shuttering, reinforcement and Admixtures in recommended proportion (as per IS:9103) to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer in charge.				-
(a)	041011	All work upto plinth level including raft foundation of washable aprons, HS tank, pile cap, footings of FOB and Platform shelter etc.	cum	165.84	3,341.60	554,170.94
(b)	041012	All works in buildings above plinth level upto floor two level	cum	147.48	3,619.33	533,778.79
(c)	041015	In kerbs, steps and the likes etc.	cum	66.28	3,202.49	212,261.04
(d)	046010	Extra for RCC work in superstructure above floor two level for every floor or part thereof	cum	442.44	295.30	130,652.53
		Sub-Total				2,607,802.17

VAKYADAV

Name of work:-Construction of Railway Spans and adjacent Viaduct Spans of 04 Nos. ROBs (excluding approaches) in lieu of level crossing No. 36/C/T at IR Chainage 559/15-17 between Pahleja-Karwandia, No. 74/C/E at IR Chainage 651/17-19 between Saidraja-Chandauli Majhwar, No. 76/C/E at IR Chainage 656/9-11 between Saidraja-Chandauli Majhwar and No. 83/B/T at IR Chainage 669/21-23 between Fly Over Cabin - Junction Cabin Mughalsarai Yard of Mughalsarai division of East Central Railway

Schedule B-VI

SN	USSOR-2012ECR	Description	unit	Qty	Rate	Amount
1	192010	Earthwork in excavation for foundations and floors of the bridges, retaining walls etc. including setting out, dressing of sides, ramming of bottom, getting out the excavated material, back filling in layers with approved material and consolidation of the layers by ramming and watering etc. including all lift, disposal of surplus soil upto a lead of 300m, all types of shoring and strutting with all labour and material complete as per drawing and technical specification as directed by Engineer in charge				
(a)	192011	E/W in All kinds of soils	1 CUM	5,228.17	292.92	1,531,435.56
(b)	192020	Extra for the quantity of works, executed in or underwater and/or liquid mud including pumping out water as required	1 CUM	150	284.38	42,657.00
2	192030	Providing and laying Plain Cement Concrete 1:3:6 with graded stone aggregate of 40mm nominal size, in foundation and floors, retaining walls of bridges including mechanical mixing, vibrating, pumping	1 CUM	253.00	2,234.33	565,285.49
3	192040	Providing and laying in position machine mixed, machine vibrated and machine batched Design Mix Cement Concrete M35 grade (Cast in-Situ) using 20mm graded crushed stone aggregate and coarse sand of approved quality in RCC raft foundation & Pile cap including finishing, using Admixtures in recommended proportions (as per IS:9103), if approved in Mix design to accelerate or retard setting of concrete and/or improve workability without impairing strength and durability complete as per specifications and direction of the Engineer in charge. Payment for cement, reinforcement and shuttering shall be paid extra.	1 CUM	1,830	2,745.77	5,024,759.10
4	192060	Providing and laying in position machine mixed, machine vibrated and machine batched Design Mix Cement Concrete M35 grade (Cast in-Situ) using 20mm graded crushed stone aggregate and coarse sand of approved quality for the following Reinforced cement concrete structural elements up to height of 10m from foundation top level, including finishing, using Admixtures in recommended proportions (as per IS:9103), if approved in Mix design to accelerate or retard setting of concrete and/or improve workability without impairing strength and durability complete as per specifications and direction of the Engineer in charge. Payment for cement, reinforcement & shuttering shall be paid extra.				
(a)	192061	Abutment & Pier	1 cum	650	2,883.06	1,873,989.00
(b)	192062	Wing wall and Return wall	1 cum	-	3,020.34	-
(c)	192063	Abutment cap, Pier Cap, Inspection Platform & Pedestal over Pier cap, Fender wall, Diaphragm wall etc.	1 cum	2,174	3,157.63	6,864,687.62

WAK yadav

SN	USSOR-2012ECR	Description	unit		Qty	Rate	Amount
5	192070	Providing, driving and installing Bored cast in-situ Reinforced Cement Concrete piles of specified diameter and length below pile cap in M-35 grade Design Mix Cement Concrete, using 20mm graded crushed stone aggregate and coarse sand of approved quality, to carry a safe working load not less than specified, excluding the cost of casing pipe but including the cost of shoe and length of pile to be embedded in pile cap etc. complete, concreting by machine batching, machine mixing, scaffolding, using Admixture in recommended proportion (as per IS:9103), if approved in design Mix, placing with tremie pipe, chipping off of pile top to remove laitance concrete above cut off level etc., pumping and bailing out water with all labour material complete including crossing of tracks if required, as per approved drawing, specification and direction of the Engineer in charge. Length of the pile for payment shall be measured upto the bottom of pile cap excluding the mud mat. Payment for cement, casing pipe & reinforcement shall be paid extra.					
(a)	192073	Pile 1000mm diameter	1	Meter	5,550	8,244.28	45,755,758.72
6	192080	Providing, fabricating and installing casing pipe for bored piles for all diameters with specified thickness of steel plate including all labour, materials, pumping and bailing out water wherever required, complete as per technical specifications as directed by Engineer in charge This will include the weight of plate only and no cognizance will be given for the fittings, i.e. rivets and welding etc.	1	MT	166	66,812.05	11,090,800.30
7	192090	Extra for chieselling in addition to boring of piles, if chieselling is resorted to in hard rock or big stone boulders larger than 30cm depth by any means, i.e. by chiesel or manual chiesel and hammer method					
(a)	192092	1000mm diameter pile	1	Meter	25	1,216.55	30,413.75
8	192100	Conducting load testing of a single pile upto following capacity in accordance with IS:2911 (Part-IV) including installation of loading platform and preparation of pile head or construction of test cap and dismantling of test cap after test etc. with all labour, material, tool & plants, equipment, machinery, etc. complete as per drawing and specification, as directed by the Engineer					
(a)	192103	Initial load test up to 250 MT	1	Each	4	94,429.95	377,719.80
(b)	192104	Extra above 250 MT for each 50 MT	1	Each	4	12,282.86	49,131.44
(c)	192107	Rotine load test up to 250 MT	1	Each	6	76,386.05	458,316.30
9	192110	Lateral load testing of single pile in accordance with "IS Code of practice IS:2911 (Part-IV) for determining safe allowable lateral load of pile" with all labour, material, tool & plants, equipment, machinery, etc complete as per drawing and specification as directed by the Engineer					
(a)	192113	Piles with lateral load capacity of above 20 ton	1	Each	4	56,648.87	226,595.48

WAKYADAV

SN	USSOR-2012ECR	Description	unit		Qty	Rate	Amount
10	192120	Pulse Echo Test (PET) for integrity testing of piles with contractor's men, materials and machines. The rate includes cost of Inspection of site, preparation of pile head and any other unforeseen cost required for the test, submission of reports in triplicate as per satisfaction of the Engineer in Charge at site.	1	Each	146	41,814.00	6,104,844.00
11	195030	Centring and shuttering including strutting, propping etc. and removal of form for :					
(a)	195031	RCC Raft Foundation & Pile cap	1	Sqm	1,180	138.30	163,194.00
(b)	195032	Abutment, pier, wing walls and return walls	1	Sqm	1,577	227.40	358,609.80
(c)	195033	Abutment cap, Pier Cap, Inspection Platform & Pedestal over Pier cap, Fender wall, Diaphragm wall etc.	1	Sqm	8,272	230.28	1,904,876.16
12	201050	Providing and fixing in position of standard preformed sealed and slab type or strip seal elastomeric type expansion joints for Railway bridge or Road Over Bridges as per approved drawings and latest MOST/IRC specifications. The rates are inclusive of supplying, fixing with contractor's own materials, e.g. inserts, bolts, socket tubes, Neoprene sheet/cap etc., equipments, machineries, labour, all taxes, royalty, all lead & lifts, transport, testing, surface preparations, complete					
(a)	201051	For 80mm expansion	1	Meter	348	28,789.51	10,018,749.48
13	201060	Load testing of one or more spans of bridge as selected by the Engineer as per approved load test procedure following relevant IS/IRC/Railway codes with contractor's labour, deflection measuring instruments, loading materials, recoding and analyzing the load testing results including all lead & lift, etc. complete as required. The rates are all inclusive and will be paid after load test is finished and girder is cleared of the Kent ledges/loading material etc. The load shall be 1.25 times the stipulated design load, based on design load & not span					
(a)	201061	For Span design load upto 100 MT	1	Each	6	64,285.56	385,713.36
(b)	201062	Extra for every increase of 100 MT or part thereof in the span load capacity upto 800 MT	1	Each	6	63,125.55	378,753.30
14	222040	Supply and laying of coarse sand including consolidation, supply of all materials, labour, lead, lift, tools, plants, crossing of tracks as per drawing and technical specification as directed by the Engineer in charge in case loose slush is encountered at site of foundation before casting the foundation or before laying the filtering media	1	cum	-	1,386.33	-
15	222170	Providing and fixing of Drainage Spouts of 100mm UPVC complete as per drawing and Technical specification	1	Meter	2,204	359.48	792,293.92
16	222300	Dewatering of natural or accumulated water from any location. Payment to be done for Horse power of pump multiplied by pumping hours.	1	HP Hour	40	22.74	909.60

WAKYADAV

SN	USSOR-2012ECR	Description	unit		Qty	Rate	Amount
17	222360	Surface protection of Underside of Bridge Decks, Girders, Inside of Box Girders, Railings etc. of Bridges and Piers and Substructures which are not in River Bed by cleaning and drying the surface; repairing local defects, e.g. honeycombs with a paste of cement admixed with 5% by weight of cement of Polymer bonding agent, applying (@ 0.30 litre/sqm) a coat (DFT of 100-150 micron) of a translucent brown coloured modified phenolic resin based single component high performance polymeric waterproofing compound (sp. gr. 0.87, rosin content nil and a solid content of minimum 0.47%), applying (@ 0.25 litre/sqm) a top coat of a modified phenolic resin based single component waterproofing compound of grey or other shades (sp. gr. 0.85) before the base coat becomes tack-free; permitting the coatings to cure and dry naturally; the 2-coat system shall be impermeable under a water head of 20m, complete as per specification	1	Sqm	13,321	257.96	3,436,285.16
18	201020	Providing and laying in position machine mixed, machine vibrated and machine batched Design Mix Cement Concrete M-40 grade using 20mm graded crushed stone aggregate and coarse sand of approved quality for the Precast Prestressed (Post tensioned) concrete girder/Box (spans upto 30.5m) in contractor's casting yard, including finishing, using Admixtures in recommended proportions (as per IS:9103), if approved in Mix design to accelerate, retard setting of concrete, improve workability without impairing strength and durability, complete as per specifications and direction of the Engineer. Payment for Shuttering, Cement, Admixtures, reinforcement, HTS cables, anchorage cones, stressing of cables and grouting of the ducts will be done extra. Launching of girder/slab in position is not included in this item.	1	Cum	1,320	2,977.78	3,930,669.60
19	201070	Providing, fabricating & fixing in position to exact design profiles, prestressing H.T.S. cables of all classification made from Low Relaxation strands conforming to IS:14268-1995 in Prestressed Concrete girders/slabs etc. including supplying, cutting, making into cables with necessary spacers, colour coding, protecting with water soluble oil at all time, anchoring of cables, supplying and placing spiral corrugated type galvanized metal steel ducts sheathing made up of Cold Rolled Cold Annealed (CRCA) mild steel conforming to IS:513 of required diameter/thickness, vent pipe, placing, bending, routing, fixing, stressing & grouting of cable ducts with cement grout, Anchorage sets in required number with provision for future prestressing, if any including all lead and lift with contractor's own materials, labour, equipments etc. complete as per drawings & specifications. Rate also includes covering anchorage pads with epoxy mortar of approved quality to avoid corrosion. Cement for grouting to be paid separately.	1	MT	39.60	135,257.06	5,356,179.58
		Sub-Total					106,722,627.51

WAKYADAV

Name of work:-Construction of Railway Spans and adjacent Viaduct Spans of 04 Nos. ROBs (excluding approaches) in lieu of level crossing No. 36/C/T at IR Chainage 559/15-17 between Pahleja-Karwandia, No. 74/C/E at IR Chainage 651/17-19 between Saidraja-Chandauli Majhwar, No. 76/C/E at IR Chainage 656/9-11 between Saidraja-Chandauli Majhwar and No. 83/B/T at IR Chainage 669/21-23 between Fly Over Cabin - Junction Cabin Mughalsarai Yard of Mughalsarai division of East Central Railway

SCH-B-VII

SN	USSOR-2012ECR	Description	unit		Qty	Rate	Amount
1	211060	Providing and fixing 65/50 mm nominal dia B class G.I. pipe railing used in rows for footpath or anti-crash barrier railing including cost of M.S. angle and channels in vertical posts, riveting, welding / riveting, priming painting two coats, at all heights labour and material as a complete job	1	Kg	34038.91	72.95	2,483,138.48
2	211080	Providing/fixing/leaving/grouting various size HTS bolts / holding down bolts in concrete column or in other structural steel member with proper nuts, bolts, washers/plates as a complete job. Note - Cement used in grouting will be paid separately under relevant item.	1	Kg	0	79.04	-
3	211090	Providing, cutting, fabricating, treating, fixing & painting structural steel conforming to IS:2062 in access ladders, inspection platforms, Trolley refugee, railing etc. joints welded to neat finish including one coat of primer & two coats of synthetic enamel paints	1	MT	5.99	65,495.70	392,319.24
4	211140	Supplying, fitting and fixing in position true to line and level POT-PTFE bearing consisting of a metal piston supported by a disc or un reinforced elastomer confined within a metal cylinder, sealing rings, dust seals, PTFE surface sliding against stainless steel mating surface, complete assembly to be of cast steel / fabricated structural steel, metal and elastomer elements complete as per IS:2062, IS:1030, AISI:304, AISI:316, IS:6911, BS:3784, IS:3400, IS:226, BS-5400, Bridge Code and as per drawing and approved Technical Specifications. The design of the bearings shall be submitted by the manufacturers/contractor and got approved from Railway before fixing. Test report of the bearings should be got approved before the materials are lifted from the manufacturer premises. Payment is based on 250 MT capacity of Bearing.					
(a)	211141	POT-PTFE Bearing	1	MT Bearing Capacity	22840	412.94	9,431,549.60
(b)	211142	POT Bearing	1	MT Bearing Capacity	5440	388.71	2,114,582.40
5	211070	Supplying and fixing anti-slip M.S. Angles/nosing 65mmx 65mmx 8mm or any other size confirming to IS:2062 fixing 10mm dia, anchor bar 600mm c/c and fixing with main girder with M.S. flat on top of step of stair case, making anti-slip grooves 7 nos. arrangement for keeping and maintaining in position as per approved plan with all labour and material as a complete job	1	Kg	11,117.39	67.28	747,978.00
		Sub-Total					15,169,567.73

VSK Yadav

Name of work:-Construction of Railway Spans and adjacent Viaduct Spans of 04 Nos. ROBs (excluding approaches) in lieu of level crossing No. 36/C/T at IR Chainage 559/15-17 between Pahleja-Karwandia, No. 74/C/E at IR Chainage 651/17-19 between Saidraja-Chandauli Majhwar, No. 76/C/E at IR Chainage 656/9-11 between Saidraja-Chandauli Majhwar and No. 83/B/T at IR Chainage 669/21-23 between Fly Over Cabin - Junction Cabin Mughalsarai Yard of Mughalsarai division of East Central Railway

SCH-B-VIII							
SN	USSOR-2012 ECR	Description	unit		Qty	Rate	Amount
1	231040	Providing and laying water bound macadam with specified stone aggregate, stone screening and binding material including screening, sorting, spreading to template and consolidation with power road roller of 8 to 10 tonne capacity etc. Complete					
(a)	231041	Sub-base with stone aggregate 90mm to 45mm including stone screening 13.2mm size	1	cum	450	1,925.10	866,295.00
(b)	231042	Base course with 63mm to 45mm size including stone screening 13.2mm size	1	cum	225	1,691.15	380,508.75
(c)	231043	Base course with 53mm to 22.4mm size including stone screening 11.2mm size	1	cum	225	1,955.22	439,924.50
2	233010	Providing and applying tack coat using bitumen emulsion (Rapid setting) complying with IS:8887-1995, spraying the bitumen emulsion with mechanically operated spray unit, cleaning and preparing the existing road surface as per specification					
(a)	233011	On W.B.M @ 0.4kg/sqm	1	Sqm	1,500	22.20	33,300.00
3	233030	Providing and laying 2.5cm premix carpet surfacing with 2.25cum and 1.12cum of stone chippings of 13.2mm size and 11.2mm size respectively and 180kg of hot bitumen per 100sqm over a tack coat including consolidation with road roller of 6 to 8tonne capacity etc. complete (tack coat to be paid separately)					
(a)	233031	with paving asphalt 80/100 heated and then mixed with solvent at the rate of 70 gram per kg of asphalt	1	Sqm	1,500	153.43	230,145.00
4	235010	Providing and laying seal coat of premixed fine aggregate (passing 2.36mm and retained on 180micron sieve) with bitumen using 128 kg of bitumen of grade 80/100 bitumen and 0.60cum of fine aggregate per 100sqm of road surface including rolling and finishing with road roller all complete. Note - This should not be operated along with Hot mix carpeting	1	Sqm	1,500	48.09	72,135.00
3	237010	Providing and fixing Cat's Eye (Glow studs) heavy integral stem, reflective, aluminium die cast with elegant finish of size 100mmx100mm and 20mm high having a stem of 50mm (or 12mm dia. 90mm long) screwed and nailed to fix into the road surface or at the nosing of the central verge. The road studs should have reflectors fitted on one side of the studs (3 nos. 7 element or 1 no. 29 element reflector) complete	1	Each	504	553.51	278,969.04
4	236070	Painting road surface marking with adequate number of coats to give uniform finish with ready mixed road marking paint conforming to IS:164, on bituminous surface in white/yellow shade including cleaning the surface of all dirt, scales, oil, grease and foreign material etc. complete					
(a)	236071	New work (minimum two coats)	1	Sqm	201.60	86.66	17,470.66
		Sub-Total					2,318,747.95

Vakya

Name of work:-Construction of Railway Spans and adjacent Viaduct Spans of 04 Nos. ROBs (excluding approaches) in lieu of level crossing No. 36/C/T at IR Chainage 559/15-17 between Pahleja-Karwandia, No. 74/C/E at IR Chainage 651/17-19 between Saidraja-Chandauli Majhwar, No. 76/C/E at IR Chainage 656/9-11 between Saidraja-Chandauli Majhwar and No. 83/B/T at IR Chainage 669/21-23 between Fly Over Cabin - Junction Cabin Mughalsarai Yard of Mughalsarai division of East Central Railway

SCH-B-XII

SN	USSOR-2012 ECR	Description	unit	Qty	Rate	Amount
1		Any items of USSOR 2012 of EC Rly, which are not covered in above schedule - A, Schedule B-I to B-VIII, Schedule C-I & C-II,	% above or %below	LS amount		5,000,000.00
		Sub-Total				5,000,000.00

AK Yadav

Name of work:-Construction of Railway Spans and adjacent Viaduct Spans of 04 Nos. ROBs (excluding approaches) in lieu of level crossing No. 36/C/T at IR Chainage 559/15-17 between Pahleja-Karwandia, No. 74/C/E at IR Chainage 651/17-19 between Saidraja-Chandauli Majhwar, No. 76/C/E at IR Chainage 656/9-11 between Saidraja-Chandauli Majhwar and No. 83/B/T at IR Chainage 669/21-23 between Fly Over Cabin - Junction Cabin Mughalsarai Yard of Mughalsarai division of East Central Railway

SCH-C-I							
SN	USSOR-2012 ECR	Description	unit		Qty	Rate	Amount
1	033060	Supplying and using Cement at worksite:					
(a)	033061	Ordinary Portland Cement Grade -43	1	MT	5,447	6,631.36	36,121,017.92
		Sub-Total					36,121,017.92

VAKYADAR

Name of work:-Construction of Railway Spans and adjacent Viaduct Spans of 04 Nos. ROBs (excluding approaches) in lieu of level crossing No. 36/C/T at IR Chainage 559/15-17 between Pahleja-Karwandia, No. 74/C/E at IR Chainage 651/17-19 between Saidraja-Chandauli Majhwar, No. 76/C/E at IR Chainage 656/9-11 between Saidraja-Chandauli Majhwar and No. 83/B/T at IR Chainage 669/21-23 between Fly Over Cabin - Junction Cabin Mughalsarai Yard of Mughalsarai division of East Central Railway

SCH-C-II

SN	USSOR-2012 ECR	Description	unit	Qty	Rate	Amount	
1	045010	Supplying reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete:					
(a)	045016	Thermo-Mechanically Treated Bars 500D	1	KG	1,688,927	64.46	108,868,234.42
		Note: The contractor shall quote the rate for TMT Bars of Grade 500D					
		Sub-Total				108,868,234.42	

Note for Stage Payment:

- i) The material shall be delivered at site and properly stored under covered sheds in measurable stacks
- ii) The quantities of materials shall be brought to the site only in such installments that would facilitate smooth progress of work and consumed in reasonable time.
- iii) Proper accountal in the material register to be maintained in the prescribed format at the site for the receipt and use of the material.
- iv) Ownership of such material shall be deemed to vest with the DFCCIL for which the contractor should submit an indemnity bond in prescribed format
- v) Before releasing the stage payment, the contractor shall insure the material at his own cost in favour of DFCCIL against theft, damages, fire etc.
- vi) Stage payment in all such cases not be more than 75% of the rate of steel awarded in the contract. The balance payment shall be released only after the material is actually consumed in the work.
- vii) The price variation claim for steel would continue to be governed as per extant PV clause and with reference to delivery at site.

VAKYADAV