

Table 10.1-1 INDICATIVE LIST OF EQUIPMENT TO BE MONITORED AND CONTROLLED AT REMOTE LOCATIONS

Equipment	TSS	SSP	SP	ATS (Auto Transformer Station/Post) (If any)	Stations	OCC Control Room
Traction Transformers	√	0	0	0	0	0
Auto Transformers	√	√	√	√	0	0
DP Circuit Breakers for 2X25 KV AT system	√	0	√	0	0	0
DP Interruptors for 2X25 KV AT system	√	√	√	0	0	0
Motorised Isolators for 2X25 KV AT system	√	√	√	√	√	0
LA on secondary end of transformer	√	√	√	√	0	0
132kV Circuit Breakers	√	0	0	0	0	0
132kV Isolators	√	0	0	0	0	0
LA on primary side of Transformer	√	0	0	0	0	0
Power Quality Improvement Equipment	√	0	0	0	0	0
Battery Chargers	√	√	√	√	√	√
Auxiliary Transformers	√	√	√	√	√	0
Low Voltage Distribution Boards	√	√	√	√	0	√
Current and Potential Transformers	√	√	√	0	0	0
Doors and gate contacts	√	√	√	√	0	0
Intruder alarms	√	√	√	√	√	√
Fire alarm system	√	√	√	√	0	√
Automatic Fault Locator	√	√	√	√	0	0
CCTV	√	0	0	0	0	0
UPS	0	0	0	0	0	√

√	Quantity as per Design
---	------------------------