

Supplementary Clarifications to Pre-Bid Queries

INVITATION FOR BID (IFB) No: HQ/EN/EC/Track/MGS-DGO&KWDN-CPBH-SEBN dated 11.07.2016

Name of Work: Design, Supply and Construction of Track & Track related works including Testing & Commissioning for double track electrified railway line on Design Build Lump Sum Basis from Mughalsarai to New Sonnagar and Chirailapathu (excluding New Karwandiya – New Durgauti Section) of Eastern Dedicated Freight Corridor.

SN	Bid Document Part/Section/Clause No. /Page	Reference/Clause	Queries by Bidders	Clarification of DFCCIL
1	Clause-4.1.1 (e) Track Works - Fencing Part-2 Section-5, page 60 of 189	Wherever DFC alignment is passing through/ adjacent to Indian Railway yards a provision of a permanent continuous unscalable but see-through fencing made up of steel section between Indian Railways and DFC tracks shall be made covering a length between outer most points and crossings only on one side between IR and DFC tracks	As per the referred clause, fencing shall be provided by the Contractor in between the DFC and IR tracks wherever DFC alignment is passing through/ adjacent to IR yards. To enable contractor to calculate the fencing length in between the IR and DFC tracks request you to provide the maximum length of platform for each IR stations that are parallel to the proposed works.	Please refer para-4.1.1 (e) at Page- 60-61 of 189 of Part-2, Section-V, Volume-1 of Bid Document. Details of IR yards have been shown in Plan & Profile provided in Part-4 Reference Documents of Bid Document. These Plans & Profiles may please be referred.
2	Part- 4 : Reference Document Site Data i. Formation alignment (Plan & Profile) 61A to 61 C	Sone Bridge drawing 61 A- SONE BRIDGE 00 To 3060.pdf	The referred document "61A- SONE BRIDGE 00 To 3060.pdf" is not readable/legible. Request you to provide a legible copy of the document.	Details of Important Bridge (Sone) between Ch. 00 to 3060 have been given in three sheets i.e. 61A, 61B & 61C. These three sheets may be referred collectively for any details.
3	Part - 4 : Reference Document Site Data iii. Location of LCs	Level Crossings LOCATION OF LEVEL CROSSING	Road width at level crossings are not mentioned in the given list. Request you to provide the road width of each level crossings for quantification purpose.	Details of each LC can also be seen from Plan & Profile provided in Part-4, Reference Documents of Bid Document. Please also refer ITB para 6.2 on page-14 of Bid Document.
4	Clause- 4.1.3 Works in Station area and yards Part 2, Section-5, Page-61 of 189 & Plan & Profile MGS-DGO 107000 To 108000 Part-4 : Reference Document	IR Yard remodelling work & Insertion of turnout Contractor shall validate the yard plans provided in the bidding document for crossing and junction stations. However, IR yard remodelling work, shifting of Points and crossing, insertion of turn out or any Civil work of IR yards is not a part of the scope of work of this contract.	From the referred clause 4.1.3 of Part 2, we understand that IR yard remodelling work, shifting of Points and crossing, insertion of turn out or any Civil work of IR yards is not a part of the scope of work of this contract. However, in the referred drawing "19-PP MGS-DGO 107000 To 108000.pdf" IR Yard remodelling work and turnouts insertion in between ch. 107300 to 107600 are shown as part of the scope of work of this contract. Kindly Clarify	DFC track is passing parallel to IR in between ch. 107000 to 108000 and there is no turnout connecting DFC/IR at this location. Please refer 'Note' given below para 2.1 of Part-2 Section-V, Volume-1 on page-60 of Bid Document.

5	<p>Clause 4.1.3 Works in Station area and yards Part-2 Section-5, Page-61 of 189 & Dwg - GAQ CONNECTION PLAN Part-4 : Reference Document</p>	<p>Scope of Points & Crossings in IR alignment</p> <p>Contractor shall validate the yard plans provided in the bidding document for crossing and junction stations. However, IR yard remodelling work, shifting of Points and crossing, insertion of turn out or any Civil work of IR yards is not a part of the scope of work of this contract.</p>	<p>From the referred clause 4.1.3 of Part 2, we understand that IR yard remodelling work, shifting of Points and crossing, insertion of turn out or any Civil work of IR yards is not a part of the scope of work of this contract. However, in the referred drawing "YP-2 GAQ CONNECTION PLAN" the turnouts given at SRJ ch. 968, 1049 & 1055 are shown as part of the scope of work of this contract.</p> <p>Kindly Clarify</p>	<p>Turnout insertion in IR lines is not in the scope of work of this bid. Please refer 'Note' given below para 2.1 of part-2, Section-V, Volume-1 on page 60 of Bid Document.</p>
6	<p>Clause -4.1.3 Works in Station area and yards Part- 2 Section-5, Page-61 of 189 & Dwg. DFC NEW SONNAGAR PLAN Part-4 : Reference Document</p>	<p>Scope of Points & Crossings in IR alignment</p> <p>Contractor shall validate the yard plans provided in the bidding document for crossing and junction stations. However, IR yard remodelling work, shifting of Points and crossing, insertion of turn out or any Civil work of IR yards is not a part of the scope of work of this contract.</p>	<p>From the referred clause 4.1.3 of Part 2, we understand that IR yard remodelling work, shifting of Points and crossing, insertion of turn out or any Civil work of IR yards is not a part of the scope of work of this contract. However, in the referred drawing "YP-6 DFC NEW SONNAGAR PLAN" the turnouts given at SRJ ch. 999.76, 1074.75, 1256.47 & 1256.47 are shown as part of the scope of work of this contract.</p> <p>Kindly Clarify</p>	<p>Turnout insertion in IR lines is not in the scope of work of this bid. Please refer 'Note' given below para 2.1 of part-2, Section-V, Volume-1 on page 60 of Bid Document.</p>
7	<p>Clause - 4.1.3 Works in Station area and yards Part- 2 Section-5, Page-61 of 189 & Dwg -DFC CHIRAILAPATHU Part- 4 : Reference Document</p>	<p>Scope of Points & Crossings in IR alignment</p> <p>Contractor shall validate the yard plans provided in the bidding document for crossing and junction stations. However, IR yard remodelling work, shifting of Points and crossing, insertion of turn out or any Civil work of IR yards is not a part of the scope of work of this contract</p>	<p>From the referred clause 4.1.3 of Part 2, we understand that IR yard remodelling work, shifting of Points and crossing, insertion of turn out or any Civil work of IR yards is not a part of the scope of work of this contract. However, in the referred drawing "YP-7 DFC CHIRAILAPATHU" the turnouts given at SRJ ch. 416, 429, 527 & 1329, 1427, 1500 are shown as part of the scope of work of this contract</p> <p>Kindly Clarify</p>	<p>Turnout insertion in IR lines is not in the scope of work of this bid. Please refer 'Note' given below para 2.1 of part-2, Section-V, Volume-1 on page 60 of Bid Document.</p>